

ATLANTIC TESTING LABORATORIES, LIMITED

atl

Box 29
Canton, N.Y. 13617
(315) 386-4578

Box 356
Cicero, N.Y. 13039
(315) 699-5281

March 16, 1989

U.S. Army Engineering Division, New England
424 Trapelo Road
Waltham, MA 02254-9149


Attn: Chief, Engineering Division, NEDED

Re: Delivery Order No. 0008
Birch Hill Dam, South Royalston, MA
ATL Project No. CD033-88

Gentlemen:

Enclosed are one original and two copies of the
referenced report for your review.

Sincerely,


Spencer F. Thew, P.E./L.S.

SFT/smf

Encs.

SECTION I
Birch Hill Dam Piezometer Installation
South Royalston, Massachusetts

Contract No. DACW33-87-D-0007
Delivery order No. 0008

Contracting Officer:

Stanley J. Murphy, Lt. Colonel, CE
Deputy Division Engineer

PREPARED FOR: U. S. Army Corps of Engineers
New England Division
424 Trapelo Road
Waltham, MA 02254-9149

PREPARED BY: Atlantic Testing Laboratories, Limited
P.O. Box 29
Canton, New York 13617

ATL Report No. CD033-1-12-88

December 1988

SECTION 2
TABLE OF CONTENTS

SECTION 1	Title Page
SECTION 2	Table of Contents
SECTION 3	Scope of Investigation a. Delivery Order b. Project Site c. Purpose d. Scope of Work
SECTION 4	Quality Control a. General Certification Statement b. Records Taken c. Equipment Used d. Procedures
SECTION 5	Summary of Daily Activities and Telephone Log Table I Daily Activities Table II Telephone Log
SECTION 6	Chain of Custody Log
SECTION 7	Safety Reports
SECTION 8	Field Inspector's Logs Birch Hill Dam Drawings General Plan Piezometer Location Plan Cross Sections (3) Piezometer Installation Detail (2)
SECTION 9	Other Records Taken a. Survey Notes

SECTION 3

SCOPE OF INVESTIGATION

a. Delivery Order No. 0008

CD033

CHECKED BOX APPLIES		<input checked="" type="checkbox"/> ORDER FOR SUPPLIES OR SERVICES			<input type="checkbox"/> REQUEST FOR QUOTATIONS NO. RETURN COPY(IES) OF THIS QUOTE BY (THIS IS NOT AN ORDER. See DD Form 1155r)			PAGE 1 OF 3	
1. CONTRACT PURCH ORDER NO. JW33-87-D-0007		2. DELIVERY ORDER NO. 0008		3. DATE OF ORDER 88 SEP 23		4. REQUISITION/PURCH REQUEST NO. GEB 88-29		5. CERTIFIED FOR NATIONAL DEFENSE UNDER DMS REG 1 DO	
ISSUED BY: Dept. of the Army New England Division, Corps of Engineers 424 Trapelo Road Waltham, MA 02254-9149 Buyer/Symbol: Kewer/CENED-CT-C Phone: AC 617-647-8414				7. ADMINISTERED BY (other than G) CODE		8. DELIVERY FOB <input checked="" type="checkbox"/> DEST <input type="checkbox"/> OTHER (See Schedule (f other))			
9. CONTRACTOR/QUOTER CODE				FACILITY CODE		10. DELIVER TO FOB POINT BY: In accordance with Paragraph 6 of the Scope of Work		11. CHECK IF BUSINESS IS <input checked="" type="checkbox"/> SMALL <input type="checkbox"/> SMALL DISADVANTAGED <input type="checkbox"/> WOMEN-OWNED	
NAME AND ADDRESS Atlantic Testing Laboratories, Limited P.O. Box 29 Canton, New York 13617				12. DISCOUNT TERMS NET		13. MAIL INVOICES TO: Finance & Accounting Officer at issuing office			
14. SERVICES FOR: U.S. Army Engineer Division, New England ATTN: Geotechnical Engineering Branch 424 Trapelo Road Waltham, MA 02254-9149				15. PAYMENT WILL BE MADE BY: Finance & Accounting Officer U.S. Army Engineer Division, N.E. 424 Trapelo Road Waltham, MA 02254-9149		MARK ALL PACKAGES AND PAPERS WITH CONTRACT OR ORDER NUMBER			
16. DELIVERY <input checked="" type="checkbox"/> This delivery order is subject to instructions contained on this side of form only and is issued in accordance with and subject to terms and conditions of above numbered contract.									
PURCHASE <input type="checkbox"/> Reference your General Provisions of Purchase Order on DD Form 1155r (EXCEPT CLAUSE NO. 12 APPLIES ONLY IF THIS BOX <input type="checkbox"/> IS CHECKED, AND NO. 14 IF THIS BOX <input type="checkbox"/> IS CHECKED); special provisions furnish the following on terms specified herein, including, for U.S. purchases, and delivery as indicated. This purchase is negotiated under authority of									
17. COUNTING AND APPROPRIATION DATA: LOCAL USE 3123 O&M CE Civil J10207400K0000 (MD)									
18. SBSA GEB STATUS MAK/ckh									
19. SCHEDULE OF SUPPLIES/SERVICES									
20. QUANTITY ORDERED: APPROX.		21. UNIT		22. UNIT PRICE		23. AMOUNT			
ESTIMATED									
LINE ITEM NO.		Furnish the necessary personnel and equipment for installation of piezometers at Birch Hill Dam, South Royalston, MA, in accordance with Attachment No. 1.		APPROX.					
1.0		GEOTECHNICAL FIELD INSPECTOR SERVICES							
1.2		Geotechnical Inspector		240		HR		\$ 42.00 \$10,080.00	
1.3		Per Diem - Overnight Stay		32		DAY		50.00 1,600.00	
1.4		Mileage from Waltham, MA & Return		240		MI		.35 84.00	
* If quantity accepted by the Government is same as quantity ordered, indicate by ✓ mark. If different, enter actual quantity accepted below quantity ordered and encircle.				24. UNITED STATES OF AMERICA		25. TOTAL \$65,460.00		26. DIFFERENCES	
27. SHIP NO.				28. D.O. NUMBER NO.		29. INITIALS		30. AMOUNT VERIFIED CORRECT FOR	
31. PAYMENT <input type="checkbox"/> COMPLETE <input type="checkbox"/> PARTIAL <input type="checkbox"/> FINAL				32. PAID BY		33. CHECK NUMBER		34. BILL OF LADING NO.	
35. RECEIVED AT				36. RECEIVED BY		37. DATE RECEIVED		38. TOTAL CONTAINERS	
39. RECEIVED AT				40. RECEIVED BY		41. DATE RECEIVED		42. S/R ACCOUNT NUMBER	
43. RECEIVED AT				44. RECEIVED BY		45. DATE RECEIVED		46. S/R VOUCHER NO.	

STANDARD FORM 36, JULY 1965 GENERAL SERVICES ADMINISTRATION FED. PROC. REG. 101 CFR 1.16-101 Exception Approved March 1977		CONTINUATION SHEET		REF. NO. OF DOC. BEING CONTD. Delivery Order No. 0008 DACW33-87-D-0007		PAGE 2	OF 3
NAME OF OFFEROR OR CONTRACTOR ATLANTIC TESTING LABORATORIES, LIMITED							
LINE NO. TRACT	SUPPLIES/SERVICES	QUANTITY	UNIT	UNIT PRICE	AMOUNT		
2.0	GEOTECHNICAL SERVICES AND REPORT	APPROX.				ESTIMATED	
2.1	Geotechnical Report	1	JOB	55% of Line Item 1.2	5,544.00		
3.0	SURVEYING						
3.1	Mobilization and Demobilization	1	JOB	350.00	350.00		
3.2	Mileage to and from Waltham, MA	120	MI	.35	42.00		
3.4	Survey Crew and Equipment	1	DAY	560.00	560.00		
3.5	Overnight Per Diem for Survey Crew	1	DAY	100.00	100.00		
3.6	Data Reduction and Plotting	1	JOB	80% of Line Item 3.4	448.00		
6.0	MOBILIZATION AND DEMOBILIZATION ONE DRILL RIG, CREW AND AUXILIARY EQUIPMENT						
6.1	Mobilization and Demobilization	2	JOB	1,100.00	2,200.00		
3	Mileage from/to Manchester, New Hampshire	240	MI	1.15	276.00		
6.5	Standby time/on site moves	90	HR	80.00	7,200.00		
4.0	DRIVE SAMPLE BORING, UNCASSED HOLE						
4.1	0-50 ft. depth	142	LF	25.00	3,550.00		
4.2	51-150 ft. depth	42	LF	40.00	1,680.00		
8.0	DRIVING AND PULLING CASING						
8.2	HX and 6-inch size	406	LF	30.00	12,180.00		
9.0	DRIVE CASING AND/OR PIPE AND LEAVING IN PLACE						
9.6	Pipe (4" I.D., 1/4" Wall)	80	LF	25.00	2,000.00		
10.0	CASING AND PIPE						
10.4	Pipe (4" I.D., 1/4" Wall)	80	LF	9.00	720.00		
12.0	DIAMOND CORE DRILLING VERTICAL						
12.4	4 X 5-1/2 size, Double Tube Barrel	32	LF	75.00	2,400.00		

CONTINUATION SHEET

REF NO OF DOC BEING CONTD
 Delivery Order No. 0008
 DACW33-87-D-0007

PAGE 3 OF 3

NAME OF OFFEROR OR CONTRACTOR

ATLANTIC TESTING LABORATORIES, LIMITED

ITEM NO	SUPPLIES/SERVICES	QUANTITY	UNIT	UNIT PRICE	AMOUNT
		APPROX.			ESTIMATED
24.0	PIEZOMETER				
24.1	Casagrande type/or equal, 0-50 ft. depth	639	LF	16.00	10,224.00
24.2	Casagrande type/or equal, over 50 ft. depth	39	LF	18.00	702.00
31.0	LIGHT LUMBER FOR SHORING EXCAVATION				
31.1	Light Lumber for Shoring Excavation	2	MBF	800.00	1,600.00
34.0	TRUCK WITH TOWING WINCH				
34.1	Truck with Tow Winch	24	HR	80.00	1,920.00

ATTACHMENT NO. 1

GEB REQUISITION 88-29- DACW 33-87-D-0007

DELIVERY ORDER NO. 0008

INSPECTION AND EXPLORATION INSTRUCTIONS

PROJECT: Birch Hill Dam Piezometer Installation

SITE: Birch Hill Dam, South Royalston, MA

PURPOSE: To determine internal phreatic surface

1. SCOPE OF INVESTIGATIONS

a. Eight borings shall be completed, four at Sta 7+00 and four at Sta 10+50. Offsets are shown on Attachments 2, 3, and 4. Field locations will be staked by New England Division personnel prior to start of work. Plan and section of the areas to be drilled are shown on Attachments 2, 3, and 4.

b. Borings will be advanced using six inch or four inch casing to the elevations indicated on the piezometer installation details. Soil sampling shall be continuous and shall be performed using SPT procedures in sands, and a 2-1/2 inch I.D. sample spoon in gravels. Sampling instructions particular to each boring are shown on the piezometer installation details.

c. All elevations and installation details are subject to change as the work progresses. Close coordination with GEB personnel is required during drilling operations to determine final piezometer elevations and installation details. The objective is to locate the upper piezometer tips in the pervious sand and gravel layer located at the interface of the embankment and foundation. The lower piezometer tips will be located in the less pervious m-f sands and fine sandy silts.

d. Only Revert drilling fluid (or other biodegradable drilling fluid) shall be permitted to keep the hole open.

e. Atlantic Testing shall supply all sample jars. The entire sample shall be saved and labeled.

f. Piezometers shall be installed as shown on the attached pages (Attachments 5 through 12). The top riser pipes of double piezometers shall be of different colors to distinguish upper and lower tip settings. The color of each piezometer number shall be noted on the boring logs. Final locations of piezometer tips shall be approved by New England Division personnel.

g. All piezometers shall be capped with one solid 10 foot piece of 4 inch pipe grouted in the hole and backfilled with sand only. A vented screw cap shall be provided for each of the six slope holes and a flush fitting water gate box or equivalent shall be provided for the two crest holes. Six inch casing shall not be used to cap the piezometers because the dam tenders are not supplied with 36" pipe wrenches. Six inch casing can only be used if the top is modified down to a four inch cap.

h. A sand filter shall be placed around each piezometer to the depth and elevation shown on the piezometer detail. Filter sand below the piezometer shall be tamped.

i. Falling-head permeability tests shall be performed on each piezometer after installation and the results recorded.

j. A geotechnical inspector shall act as field inspector while performing the borings. The inspector shall provide telephone reports to Mr. Anthony Firicano, Corps of Engineers, at telephone 617-647-8396 at least once every working day and upon completion of each boring. The alternate point of contact is Mr. John Hart at telephone 617-647-8389.

k. All samples shall be delivered to the Corps of Engineers Headquarters in Waltham, Massachusetts. Sample delivery shall be coordinated with the Director, NED Materials and Water Quality Laboratory at telephone 617-647-8367/8392.

2. SITE CONDITIONS

All borings are located on an earth and rockfill dam which is owned and operated by the Corps of Engineers. Six borings are located on the rockfill slopes of this dam. Means of locating and securing the drill rig to these slopes must be provided.

3. COORDINATION

The field inspector shall coordinate all work with the following NED personnel: Mr. Anthony Firicano 617-647-8396, Geotechnical Engineering Br., Waltham and Mr. James H. Bacon at 508-249-4467, Project Manager, Birch Hill Dam. Mr. Anthony Firicano shall be notified one week prior to the start of work.

4. EXPLORATION DESIGNATION

Borings shall be numbered FD-88-1 to FD-88-8 in the order of their completion.

5. GOVERNMENT REVIEW

The Government will review the draft submittal as well as the completed work. Subsequent to such review, the Contractor shall accomplish any corrections which may be directed as the result of the Government review.

6. COMPLETION SCHEDULE

Services under this delivery order shall start within 7 calendar days after receipt of the delivery order. Duration of field work is estimated to be twenty work days. The geotechnical report shall be submitted in draft format for review by the Government no later than seven calendar days after completion of the field work. Government review will take approximately ten calendar days from receipt of draft report. The final geotechnical report shall be submitted no later than seven calendar days after receipt of the corrected draft report including the action taken on possible comments.

7. QUALITY CONTROL

You will be held responsible for the quality of the submittals and for all damages caused the Government as a result of your negligence in the performance of any services furnished under the contract.

Although submissions required by your contract are technically reviewed by the government, it is emphasized that your work must be prosecuted using proper internal controls and review procedures. The letter of transmittal for each submission which you make shall include a certification that the submission has been subjected to your own review and coordination procedures to insure (a) completeness for each discipline commensurate with the level of effort required for that submission, (b) elimination of conflicts, errors and omissions and (c) the overall professional and technical accuracy of the submission. Documents which are significantly deficient in any of these areas will be returned to you for correction and/or upgrading prior to completing our review. Contract submission dates will no be extended if a resubmission of draft material is required for this reason.

BIRCH HILL DAM

PIEZOMETER DEPTHS AND ELEVATIONS


PIEZOMETER *****	TOP OF BORING ELEVATION *****	APPROXIMATE DEPTH OF BORING *****	BOTTOM OF BORING ELEVATION *****	PIEZ. TIP (S) ELEVATION *****	DEPTH 6 IN CASING *****
PZ-10 A&B	855	56	799	800 811	45
PZ-11 A&B	864	65	799	800 813	52
PZ-12 A&B	848	49	799	800 813	36
PZ-13 A&B	832	33	799	800 815	18
PZ-14 A&B	855	56	799	800 819	37
PZ-15 A&B	864	65	799	800 817	48
PZ-16 A&B	848	49	799	800 815	34
PZ-17 A&B	832	33	799	800 815	18

27 Sept 49

SUBJECT Birch Hill Dam NF

COMPUTATION Piezometer Installation, PZ-10 A & B Sta 7+00

COMPUTED BY CE CHECKED BY _____ DATE 28 Sep 49



NOTES:

1. 6 in. ID hole to El. 810,
4 in. ID hole below
El. 810.
2. Sampling:
 - a. El. 855 to 820 - No sample
 - b. El. 820 to Bottom of hole
continuous samples.

DEPARTMENT OF THE ARMY NEW ENGLAND DIVISION CORPS OF ENGINEERS WALTHAM, MASS.	
DES. BY	Birch Hill Dam Piezometer Installation
DR. BY	
CK. BY	
GEOTECH. ENG. BR. SCALE: SK. NO. <u>ATTACH 5</u> DATE:	

27 Sept 49


SUBJECT Birch Hill Dam, MA

COMPUTATION Piezometer Installation, PZ-11A & B, Sta. 7+00

COMPUTED BY AF

CHECKED BY _____

DATE 23 July 53



NOTES:

1. 6 in. ID hole to EI. 812
4 in. ID hole below EI. 812

2. Sampling:

- a. EI. 864 to 820 - No Sample
- b. EI. 820 to bottom of hole - continuous samples.

DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION
CORPS OF ENGINEERS
WALTHAM, MASS.

DES. BY

DR. BY

CK. BY

Birch Hill Dam

PIEZOMETER INSTALLATION

GEOTECH. ENG. BR.

SCALE:

SK. NO. ATTACH 6

DATE:

27 Sept 49

SUBJECT Birch Hill Dam, MA

COMPUTATION Piezometer Installation, PZ-12 A&B, Size 7-20

COMPUTED BY CE

CHECKED BY _____

DATE


23 JUL 50

NOTES:

1. 6 in. ID hole to El. 812
4 in. ID hole below
El. 812.

2. Sampling:

- a. El. 848 to 820 - No sample req'd.
- b. El. 820 to bottom of hole
continuous samples



DEPARTMENT OF THE ARMY NEW ENGLAND DIVISION CORPS OF ENGINEERS WALTHAM, MASS.	
DES. BY	BIRCH HILL DAM PIEZOMETER INSTALLATION
DR. BY	
CK. BY	
GEOTECH. ENG. BR. SCALE:	
SK NO ATTACH 7 DATE:	

SUBJECT Birch Hill Dam, MA

 COMPUTATION Estimate, 2-11-49 PZ-13 A & B, 220 7-00

 COMPUTED BY RF

CHECKED BY _____


 DATE 29 July 49

NOTES:

1. 6 in. I.D. hole to El. 814
4 in. I.D. hole below
El. 814.

2. Sampling :

- a. El. 832 to 822 - No Sample Rqd.
- b. El. 822 to Bottom of hole
Continuous samples


 DEPARTMENT OF THE ARMY
 NEW ENGLAND DIVISION
 CORPS OF ENGINEERS
 WALTHAM, MASS.

DES. BY

DR. BY

CK. BY

 BIRCH HILL DAM
 PIEZOMETER INSTALLATION


 GEOTECH. ENG. BR. SCALE:
 SK. NO. ATTACH 8 DATE:

27 Sept 49

SUBJECT Birch Hill Dam, MA

COMPUTATION Piezometer Installation PZ-14 Sta 10+30

COMPUTED BY RF CHECKED BY _____ DATE 10/10/49



NOTES:

1. 6 in. ID hole to EI. 826
- 4 in. ID hole below EI. 826

2. Sampling:

- a. EI. 855 to 826 - No sample
- b. EI. 826 to bottom of hole continuous samples.

DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION
CORPS OF ENGINEERS
WALTHAM, MASS.


DES. BY

DR. BY

CK. BY

BIRCH HILL DAM
PIEZOMETER INSTALLATION

GEOTECH. ENG. BR. SCALE:
SK NO ATTACH 9 DATE:

SUBJECT Birch Hill Dam U.F.COMPUTATION Piezometer Installation, PZ-15 A & B, 3-2-50COMPUTED BY A.E. CHECKED BY _____ DATE 13 July 50

NOTES:

1. 6 in ID hole to El. 816, 4 in ID hole below El. 816.
2. Sampling.
 - a. El. 864 to 824 - No Sample.
 - El. 824 to bottom of hole - continuous samples.

DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION
CORPS OF ENGINEERS
WALTHAM, MASS.

DES. BY

DR. BY

CK. BY

BIRCH HILL DAM


PIEZOMETER INSTALLATION

GEOTECH. ENG. BR. SCALE:

SK. NO. ATTACH 10 DATE:

27 Sept 49

SUBJECT Birch Hill Dam M.F.
 COMPUTATION Piezometer Installation, PZ-16 F & E. Sta. 10+50
 COMPUTED BY LT CHECKED BY _____ DATE 20 July 50



NOTES:

1. 6 in. ID. hole to El. 814
 4 in ID. hole below
 El. 814
2. Sampling:
 - a. El. 848. to 822 - No Sample
 - b. El. 822 to Bottom of
 hole - Continuous samples

DEPARTMENT OF THE ARMY
 NEW ENGLAND DIVISION
 CORPS OF ENGINEERS
 WALTHAM, MASS.

DES. BY

DR. BY

CK. BY

BIRCH HILL DAM
 PIEZOMETER INSTALLATION


GEOTECH. ENG. BR. SCALE:

SK. NO. ATTACH II DATE:

SUBJECT Birch Hill Dam IJF

COMPUTATION REZOMETER INSTALLATION PZ-17A & B

COMPUTED BY SE CHECKED BY _____ DATE 28 July 57



NOTES:

1. 6 in. ID hole to El. 814,
4 in. ID hole below El. 814

2. Sampling:

- a. El. 832 to 822 - No sample
- b. El. 822 to bottom of hole.
continuous samples.

DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION
CORPS OF ENGINEERS
WALTHAM, MASS.

DES. BY

DR. BY

CK. BY

BIRCH HILL DAM
REZOMETER INSTALLATION

GEOTECH. ENG. BR. SCALE:

SK. NO. ATTACH 12 DATE:

b. Project Site

The investigation took place on the left and right side of the earth dam at stations 7+00 and 10+50.

A General Plan, Piezometer Location Plan, three Cross Sections, and two Piezometer Installation Details are included in Section 8. These plans were provided to us in the Delivery Order. The project site is indicated on a portion of the Royalston, Mass-NH Quadrangle sheet of which a portion is reproduced and included on the following page.


c. Purpose

The purpose of the exploration and piezometer installation was to provide information regarding the internal phreatic surface.

d. Scope of Work

Inspection and exploration instructions, which were provided by the Army Corps of Engineers, New England Division, in Delivery Order No. 0008, are included in Section 3a. General inspection, exploration, and piezometer installation instructions were provided by the Army Corps of Engineers, New England Division, through the contracted Geotechnical Exploratory Work Various Locations in New England. Specific instructions and changes during the course of the work were given verbally during on-site visits and telephone conversations with a USACE representative. All new instructions and changes can be found listed in Table I, Daily Activities and Table II, Telephone Log, both included in Section 5.

Drilling, sampling and piezometer installation was performed by Atlantic Testing Laboratories' personnel using Atlantic Testing Laboratories' equipment. The test borings were advanced and sampled as indicated on Attachment No. 1 of the Delivery Order (Section 3a) and as outlined in the contract specifications. Overburden sampling was performed using a 2 ft split spoon sampler (1-3/8" I.D.) and 140 lb hammer with a 30 inch drop.



INTERIOR-GEOLOGICAL SURVEY WASHINGTON D. C. - 1962
MP 2647

BALDWINVILLE 3.8 MI.
GARDNER 3.3 MI.


ROAD CLASSIFICATION

Medium-duty

Light-duty

Unimproved dirt

State Route



QUADRANGLE LOCATION

ROYALSTON, MASS.-N. H.
N 4237.5-W 7207.5/7.5

1954


SECTION 4

QUALITY CONTROL

a. General Certification Statement

I hereby certify that the records, equipment and procedures mentioned below were used to perform the subsurface exploration described herein. I also certify that the work was performed in a professional manner and meets the requirements set forth in the Delivery Order. This report has been subject to my review and is both complete and technically accurate.

CERTIFIED December 21, 1988


Spenser F. Thew, P.E./L.S.

b. Records Taken

Pertinent drilling procedures, sampling operations, and soil classifications were noted on the following forms provided for use by the Corps of Engineers:

NED-121 Field Log of Test Boring, Summary
NED-58 & 58A Field Log of Test Boring
NED-59 Subsurface Water Observations and Boring Location Sketch

Information outlining installed piezometer characteristics were noted on the Piezometer Installation Report and the Piezometer Installation Detail. A completed series of Field Logs, the Piezometer Installation Report, Subsurface Water Observation, Boring Location Sketch, and Piezometer Installation Detail are included in Section 8.

Sample containers were labeled using ATL sample labels. The samples were accepted by Tony Firicano, USACE, on the Birch Hill Dam site on November 22, 1988.

A summary of Daily Activities and Telephone Logs are Tables I and II of Section 5. A chain of custody log is included in Section 6. The Safety Meeting Reports (NED 251), including the exposure time for ATL are included in Section 7.

c. Equipment Used

A listing of all pertinent equipment and supplies provided by Atlantic Testing Laboratories, Limited.

Drilling equipment:

- CME 45 skid mounted drill rig
- CME 75 truck mounted drill rig
- CME 850 ATV drill rig
- SW (6") casing with drive and spin shoes
- drill rod - 2 ft, 5 ft and 10 ft lengths used for sampling and turning 5-5/8" roller bits
- 1-1/2" and 3" centrifugal pumps with 200 ft of fire hose and 300 ft of 1-1/2" black plastic pipe
- split spoon samplers, 2" O.D. x 2' in length
- three 100 gallon stock tanks

Piezometer supplies:

- Casagrande piezometer 1" ID x 2' in length
- threaded 3/4" ID scheduled 80 PVC riser pipe in 10 ft lengths
- filter sand, No. 4 in 100# bags
- Bentonite well seal, 3/8" diameter peltonite pellets
- backfill material was either No. 4 filter sand or original material from the bore hole

Piezometer test equipment:

- 200 ft electronic water level indicator (RocTest Model CPR4)
- standard watch with stopwatch function

Excavation equipment:

- M-F 2244 dozer with operator

Subcontracted equipment:

- large tow truck on GMC general chassis

d. Procedures

1. Survey Procedures

- Horizontal Control - Third Order (Class I)
- Vertical Control - Third Order (Class I)

1. Sampling and Drilling Procedures

Eight (8) borings were performed at the Birch Hill Dam. Two (2) piezometers were installed in all eight (8) of the borings. The field exploration included drilling and soil sampling followed by piezometer installation and testing.

Soil sampling techniques as described in the Contract Delivery Order involved retrieving material using the Standard Penetration Test. A 1-3/8" ID by 2 ft long spoon was driven the length of the spoon or until refusal was encountered. The blow counts were recorded for each 6" of advancement. Samples were classified in the field in accordance with ASTM D-2488. Samples were taken from each soil sampling run and placed in either 16 oz or 32 oz jars with hermetically sealed lids. A chain of custody log was maintained to document custody of samples between ATL and the USACE.

The CME 45, 75 and 850 drill rigs were equipped to handle several different methods of drilling. Different techniques for advancing each hole, in conjunction with sampling were employed to best suit the situation. These systems are generally described as follows:

- SW (6) drive casing driven with 300# hammer with 24" drop.
- Auger drilling followed by driving SW (6") casing to desired depth.
- SW (6") spin casing preceded by a 5-5/8" roller bit when necessary to advance the casing.
- SW (6") spin casing until refusal is encountered; the hole was then advanced with 5-5/8" roller bit using Fluidrill drilling fluid to maintain open hole; the Fluidrill was deactivated by using Clorox.

2. After boring had been advanced to the required depth, filter sand was placed in the bottom of the hole to the specified depth. The 2 ft long porous plastic piezometer and 3/4" PVC riser pipe was lowered to the depth determined by the USACE.

Then No. 4 filter sand was added, followed by a 4 ft bentonite seal (3/8" bentonite pellets) at the specified depths. This procedure was done for each of two piezometers placed in each bore hole. The remainder of the hole above the upper piezometer was filled with either on site soils or filter sand. A 4" diameter pipe by 10 ft length of pipe was left in place around the 3/4" riser pipe for protection. The piezometer riser pipe protectors stand about 3 ft above ground. The piezometer was secured with a vented screw-on cap on the protective casing.

1. Piezometer Testing Procedures

A falling head test was performed on each piezometer after installation. This required pouring water down the pipe until it completely fills the riser and measuring the water level drop versus time. The depth was measured using an electronic water level indicator at the following scheduled time intervals: 0, 1, 5, 10, 30 minutes. However, in cases when the water dropped very rapidly, the time intervals were more closely spaced.

SECTION 5
SUMMARY OF DAILY ACTIVITIES
AND
TELEPHONE LOG

TABLE I
DAILY ACTIVITIES LOG

CD033 - BIRCH HILL DAM

Oct. 5, 1988
Wednesday

Todd Burnham, ATL driller on site 9:30 a.m. to 5:30 p.m.

- Mobilized 2000 board ft of lumber to the site to construct platforms.
- Started constructing platform at mid-slope (PZ-12) to support the skid mounted rig.
- Constructing platform, one driller - 8 hrs.

Oct. 6, 1988
Thursday

Todd Burnham, ATL driller on site 8:00 a.m. to 2:30 p.m.

- Completed construction of the drill platform at mid-slope (PZ-12).
- Todd met with Tony Firicano, USACE, at noon, walked the site and reviewed the bore hole locations.
- Constructing platform, one driller - 6.5 hrs.

Oct. 14, 1988
Friday

Todd Burnham and Scott Fox, ATL drillers on site 9:30 a.m. to 1:00 p.m.

- Mobilized the CME 850 ATV to the dam site.
- The drillers unloaded additional lumber and began positioning it for the second drill platform (PZ-13).
- Constructing platform, two drillers - 3.5 hrs.

Oct. 17, 1988
Monday

Chris Lawrence, ATL Geologist on site 6:30 a.m. to 5:30 p.m.

- Chris Lawrence met with Ed Lippman, USACE Assistant to Project Manager at Birch Hill Dam and made a site inspection.
- Mobilized dozer and CME 75 truck mounted drill to site.

Oct. 18, 1988
Tuesday

Chris Lawrence, ATL Geologist; Paul Davis, Drilling Supervisor; Mike Hawkins, Paul McAloon, Todd Burnham, Shannon Hart, ATL drill crew on site 6:30 a.m. to 6:30 p.m.

- Safety meeting held 6:45 to 7:15 a.m.
- CME 850 began making access to set up on PZ-10 (FD-88-2). It was necessary to clear surface rocks to position CME 850 and place 3" stone fill.
- First gravel truck arrived at 8 a.m.; gravel was bulldozed to make drilling platform for PZ-14 (FD-88-4) and PZ-10 (FD-88-2); 140 cy were used to construct platforms.

Oct. 18, 1988 Continued

- CME 75 began drilling PZ-11 (FD-88-1); advanced 6" (SW) casing to 64 ft; started sampling from 44 to 64 ft; terminated at 64 ft.
- Standby time for CME 850, 6:30 a.m. - 6:30 p.m., bore hole move to piezometer location on slope.
- Dozer on site 6:30 a.m. to 4:30 p.m.

Oct. 19, 1988
Wednesday

Chris Lawrence, ATL Geologist; Paul Davis, Drilling Supervisor; Mike Hawkins, Paul McAloon, Todd Burnham, Shannon Hart, ATL drill crew on site 6:30 a.m. to 7:00 p.m.

- At 6:30 a.m., CME 850 began PZ-10 (FD-88-2), spun casing to hole termination at 56 ft. Placed piezometers at depths of 44-46 ft and 53-55 ft. The upper piezometer (orange riser) and lower piezometer (grey riser). Chris Allie, USACE was on site and approved the new piezometer depth for the upper piezometer based on sample review.
- CME 75 cleaned hole to bottom of 6" casing at depth of 64 ft in PZ-11 (FD-88-1). Installed lower piezometer (grey riser) in bore hole at depth of 61-63 ft. The change in depth was approved by Chris Allie, USACE. Upper piezometer (orange riser) was installed at depth of 49-51 ft. Piezometer installation was completed, the 6" casing was removed and 4" protective pipe installed.
- CME 75 moved to PZ-15 (FD-88-3).

Oct. 20, 1988
Thursday

Chris Lawrence, ATL Geologist, on site 6:30 a.m. to 6:15 p.m.; Paul Davis, Drilling Supervisor; Mike Hawkins, Paul McAloon, ATL drill crew on site 6:30 a.m. to 5:15 p.m. Todd Burnham and Shannon Hart, ATL drill crew on site 7:15 a.m. to 7:15 p.m.

- CME 850 removed the 6" casing from PZ-10 (FD-88-2) and installed 4" protective pipe.
- The CME 850 then moved to PZ-14 (FD-88-4).
- CME 850 spent two hours clearing rocks so drilling could begin on PZ-14 (FD-88-4). Hole was advanced to approximately 29 ft.

- CME 75 completed bore hole PZ-15 (FD-88-3) and set the lower piezometer (grey riser) at a depth of 62 - 64 ft and upper piezometer (orange riser) at a depth of 45 to 47 ft.
- Drill crew drained water from rig and pumps as temperatures are expected to be below freezing tonight.
- Stand by time for CME 850 from 9 a.m. to 10:30 a.m. moving between bore holes and 2 hours clearing rocks.

Oct. 21, 1988
Friday

Chris Lawrence, ATL Geologist on site from 6:30 a.m. to 4:30 p.m.; Paul Davis, Drilling Supervisor on site 6:30 a.m. to 8:00 a.m. Mike Hawkins, Paul McAloon, ATL drill crew on-site 6:30 a.m. to 8:30 a.m.; Todd Burnham and Shannon Hart, ATL drill crew, on site 6:30 a.m. to 5:15 p.m.

- CME 850 drill crew thawed water lines and resumed drilling PZ-14 (FD-88-4) to a depth of 56 ft. Sampling was performed from 29 to 55 ft. Lower piezometer (grey riser) was installed at a depth of 53-55 ft. Upper piezometer (orange riser) placement was approved by Chris Allie, USACE, who was on site and initialed the change in depth on the log, from 34-36 ft to a depth of 40-42 ft. Pulled casing out of PZ-14 (FD-88-4) and installed protective pipe.
- CME 75 drill crew restored drill site from 6:30 to 8:00 a.m., and demobilized at 8:30 a.m.
- CME 850 drill crew restored drill site from 1:00 to 2:30 p.m., and demobilized at 6:30 p.m.
- Geologist left site approximately 1 p.m. to 4 p.m. to go to airport to pick up tractor trailer driver. Truck and trailer with rig departed site at 4:15 p.m. Drill crew remained to finish cleaning up the site.
- Dozer used to restore slope from 1-4 p.m.
- Standby time, CME 75 from 6:30 a.m. to 8:00 a.m.
- Standby time, CME 850 from 1:00 to 4:30 p.m.

Nov. 1, 1988
Tuesday

Chris Lawrence, ATL Geologist; Randy Todd and Rob Pryce, ATL drill crew, on site 9:45 a.m. to 4:30 p.m.

- CME 45 skid rig mobilized to site to perform midslope and toe piezometer installations.

- CME 45 skid rig was winched down the slope towards platform on PZ-12 (FD-88-5). Wrecker to aid in positioning drill rig was on site from 2:00 to 4:00 p.m. Heavy rain all day.
- Standby time, 9:45 a.m. to 4:30 p.m.

Nov. 2, 1988
Wednesday

Chris Lawrence, ATL Geologist; Randy Todd and Rob Pryce, ATL drill crew on site 7 a.m. to 4:45 p.m.

- Set CME 45 drill rig on platform and carried drill equipment and pumps to drill location (PZ-12).
- Standby time, 7:00 a.m. to 4:45 p.m.

Nov. 3, 1988
Thursday

Chris Lawrence, ATL Geologist; Randy Todd and Rob Pryce, ATL drill crew on site 7 a.m. to 5 p.m.

- Advanced 6" (SW) casing to 25 ft in PZ-12 (FD-88-5). Had difficulty going through surface rocks (used 4x5-1/2" core to get through surface rocks).

Nov. 4, 1988
Friday

Chris Lawrence, ATL Geologist; Randy Todd and Rob Pryce, ATL drill crew on site 6:30 a.m. to 12:45 p.m.

- Crew had to thaw pipes before drilling. Began sampling at 28 ft in PZ-12 (FD-88-5). Advanced casing to 30 ft.
- Terry Wong, USACE was on site. He reviewed the samples from the first four holes along with the logs and found everything satisfactory.

Nov. 7, 1988
Monday

Chris Lawrence, ATL Geologist on site from 1 p.m. to 5:30 p.m. Randy Todd and Rob Pryce, ATL drill crew on site 2:45 p.m. to 5:30 p.m.

- Advanced PZ-12 (FD-88-5) to 32 ft.
- Safety meeting held from 5 to 5:30 p.m.

Nov. 8, 1988
Tuesday

Chris Lawrence, ATL Geologist; Randy Todd and Rob Pryce, ATL drill crew on site 6:30 a.m. to 5:30 p.m.

- Sampled PZ-12 (FD-88-5) to 50 ft.
- Tony Firicano, USACE, arrived on site 1:40 p.m. Yellow-brown sand was encountered lower in the bore hole than expected; Tony Firicano agreed we should sample 48 - 50 ft and drill to 51 ft.

- Lower piezometer (grey riser) was installed from 48 to 50 ft and upper piezometer (orange riser) was installed from 40 - 42 ft. Began pulling casing with considerable difficulty.
- Began building platform to PZ-13 (FD-88-6) from 3:30-5:30 p.m.
- Standby time 3:30-5:30 p.m.

Nov. 9, 1988
Wednesday

Chris Lawrence, ATL Geologist; Randy Todd and Rob Pryce, ATL drill crew on site 6:30 a.m. to 5:30 p.m.

- Finished pulling casing for PZ-12 (FD-88-5) and set 4" protective pipe from 6:30-7:30 a.m.
- Finished building platform for PZ-13 and began mobilizing drill equipment down slope from 7:30 a.m. to 5:30 p.m.
- Wrecker on-site from 1:30 to 5 p.m. to assist in bore hole move to PZ-13 (FD-88-6).
- Standby time for CME 45, 7:30 a.m. to 5:30 p.m.

Nov. 10, 1988
Thursday

Chris Lawrence, ATL Geologist; Randy Todd and Rob Pryce, ATL drill crew on site 6:40 a.m. to 5:30 p.m.

- Began drilling PZ-13 (FD-88-6). Began sampling at depth of 10 ft; encountered obstruction at 18 ft; lost water circulation and had to spin casing to 20 ft; resumed sampling to bottom of hole at 34 ft.

Nov. 11, 1988
Friday

Chris Lawrence, ATL Geologist; Randy Todd and Rob Pryce, ATL drill crew on site 7 a.m. to 3 p.m.

- Cleaned bore hole PZ-13 (FD-88-6) to prepare for piezometer installation. Installed lower piezometer (grey riser) from 31 to 33 ft and upper piezometer (orange riser) from 23 to 25 ft. Pulled 6" (SW) casing and set 4" protective pipe.
- Moved drill equipment to bottom of slope and dismantled platform from 10 a.m. to 3 p.m.
- Standby time, 10 a.m. to 3 p.m.

Nov. 14, 1988
Monday

Chris Lawrence, ATL Geologist; Randy Todd and Rob Pryce, drill crew, on site 1:00 to 5:30 p.m.

- Crew left site to get new winch cable and returned to repair rig.
- Drill crew worked on platform for PZ-16 (FD-88-7).
- Safety meeting held from 6:30-7:00 p.m.
- Standby time, 3:30 to 5:30 p.m.

Nov. 15, 1988
Tuesday

Chris Lawrence, ATL Geologist and Randy Todd and Rob Pryce, ATL drill crew, on site 7 a.m. to 5:30 p.m.

- Continued building drill platform and moved drill rig and equipment to PZ-16 (FD-88-7). Had to purchase more 4x6 beams in order to raise the platform height.
- Tow truck on site from 12:30 to 5 p.m. to assist in moving skid rig. Rig was stuck in the rocks and some damage was done to the right skid. Rig was placed on platform at PZ-16 (FD-88-7).
- Standby time, 7 a.m. to 5:30 p.m.

Nov. 16, 1988
Wednesday

Chris Lawrence, ATL Geologist and Randy Todd and Rob Pryce, ATL drill crew on site 7 a.m. to 5 p.m.

- Began drilling PZ-16 (FD-88-7). Advanced 6" (SW) casing to 32 ft; sampled from 26 - 32 ft.

Nov. 17, 1988
Thursday

Chris Lawrence, ATL Geologist and Randy Todd and Rob Pryce, ATL drill crew on site 7 a.m. to 5:30 p.m.

- Advanced PZ-16 (FD-88-7) to 49 ft. Set lower piezometer (grey riser) from 46 to 48 ft and upper piezometer (orange riser) from 34 to 36 ft.

Nov. 18, 1988
Friday

Chris Lawrence, ATL Geologist and Randy Todd and Rob Pryce, ATL drill crew on site 7 a.m. to 5:30 p.m.

- Finished setting the piezometers in PZ-16 (FD-88-7), pulled casing and installed protective pipe. Prepared to move the rig off the platform. Moved drill equipment to PZ-17 (FD-88-8) from 9 a.m. to 5:30 p.m.

- Randy Todd asked if we could move drill hole PZ-17 (FD-88-8) 5 ft to the left of the stake as it was impossible to place the rig on the designated spot because of large rocks. Chris called Tony Firicano, USACE, and explained the situation. Tony agreed to the move.
- Tow truck on site 3 to 5 p.m. to move rig to platform on PZ-17 (FD-88-8).
- Standby time, 9 a.m. to 5:30 p.m.

Nov. 19, 1988
Saturday

Chris Lawrence, ATL Geologist and Randy Todd and Rob Pryce, ATL drill crew on site 6:30 a.m. to 5:30 p.m.

- Drilled PZ-17 (FD-88-8) to 10 ft where we begin sampling. Hit obstruction and drilled for about 1-1/2 hours, top of obstruction at 14', bottom at about 17 ft. Sampled to 32 ft; carried hole to 34 ft.

Nov. 20, 1988
Sunday

Chris Lawrence, ATL Geologist and Randy Todd and Rob Pryce, ATL drill crew on site 7 a.m. to 5:30 p.m.

- Lower piezometer (grey riser) was set from 31 - 33 ft and upper piezometer (orange riser) from 22 - 24 ft in PZ-17 (FD-88-8), casing was pulled and protective pipe installed. Began dismantling platform and moving drill equipment from 12:30 - 5:30 p.m.
- Standby time, 12:30 p.m. to 5:30 p.m.

Nov. 21, 1988
Monday

Chris Lawrence, ATL Geologist on site 6:30 a.m. to 8:30 a.m. and 2:00 p.m. to 5:30 p.m.; Randy Todd and Rob Pryce, ATL drill crew on site 6:30 a.m. to 7:30 a.m. and 11:30 a.m. to 5:30 p.m.

- Safety meeting held 6:30 to 7 a.m.
- Tow truck on site from 11:45 a.m. to 1 p.m. to move rig off PZ-17 (FD-88-8) and onto trailer.
- Drill crew finished dismantling platform, moving equipment to top of dam.
- Two falling head tests were run.
- Standby time, 7 a.m. to 5:30 p.m.

Nov. 22, 1988
Tuesday

Chris Lawrence, ATL Geologist on site 6:30 a.m. to 2:00 p.m. Randy Todd and Rob Pryce, ATL drill crew on site 6:30 a.m. to 6:30 p.m.

- Drilled holes to replace guard rail posts, stretched cable and finished securing the site. Started loading drill trucks. 4 - 6 p.m.
- Standby time, 6:30 a.m. to 4 p.m.

Nov. 23, 1988
Wednesday

- Randy Todd and Rob Pryce, ATL drill crew, demobilized from project.

Dec. 15, 1988
Thursday

Survey crew on site determining piezometer locations and elevations. Surveyors took static water readings in piezometers.

TABLE II
TELEPHONE ACTIVITY LOG
CD033 - BIRCH HILL DAM

Oct. 3, 1988 - Thomas Pahler, ATL to Anthony (Tony) Firicano,
Monday USACE at 10:30 a.m.

Tom told Tony that we are preparing to mobilize to the project site this week and are preparing drill platforms. Tom inquired whether it would be acceptable to construct gravel road to access PZ-10, PZ-12, PZ-14 and PZ-16 from the top of the dam. The lower piezometers would be accessed from the bottom with a skid rig and the upper piezometers will be drilled with an ATV. The gravel road is proposed to be left in place for subsequent piezometer monitoring purposes. The gravel and grading cost could be taken care of by the Corps which would present a savings in tow truck charges.

Tony expressed concern with regard to gravel, he seemed to prefer crushed stone - told him it was his option. He said he would have to contact Dam or Project Manager to determine feasibility and who would pay for the stone.

Tom told him that we would like to know ASAP so we can prepare for the project. Tony said he would call back later today.

- Spencer Thew, ATL to Ron DeFilippo, USACE at 1:00 p.m.

Spencer mentioned to Ron that Tom Pahler had been talking to Tony Firicano regarding the possibility of putting gravel fill down the slope at the four (4) boring locations that are within about 35 ft of the top of the slope. Spencer told Ron that the gravel would be about 10 ft wide and extend down to the piezometer locations. Spencer felt that the offset in cost between standby and the cost of gravel would be break even or result in a slight savings for the Corps. Ron said that they had been discussing this in the office and he would get back to Spencer when he had an answer.

- Thomas Pahler, ATL to Anthony (Tony) Firicano, USACE at 2:30 p.m.

Tony said we can go ahead with road construction to piezometer locations. Payment will probably be taken out of our tow truck item.

Tom said we'd like to make the site arrangements around Wednesday, but would be in contact for confirmation. Tony would like to show whoever is on site the piezometer locations.

Oct. 4, 1988
Tuesday

- Spencer Thew, ATL to James Bacon, Project Manager, Birch Hill Dam, USACE (508/249-4467) at 4:00 p.m.

Spencer left a message on the answering service that our drillers would be on site between 8:00 a.m. and 10:00 a.m. on Wednesday, October 5, 1988, to begin constructing drilling platforms and working on bore hole access.

Oct. 5, 1988

- Thomas Pahler, ATL to Anthony (Tony) Firicano, USACE at 8:45 a.m.

Tom called Tony regarding notification of mobilization initiation and site preparation for drill rigs. Todd Burnham, a driller, will be on-site at about 10:00 a.m. to begin constructing drilling platform for skid rig.

Tony said he may not be able to go out to the site today, but may be able to tomorrow. Tom told him that Todd will probably call in and at that time will determine what the itinerary is for the balance of the week.

Tom will call Tony again later on this date to inform him of the week's schedule and proposed activities.

- Paul Hersom, USACE to Spencer Thew, ATL at 9:35 a.m.

Paul was returning Spencer's call to Jim Bacon on October 4, 1988. Spencer indicated that our drillers would be on-site about 10:00 a.m. Paul indicated that he would wait until our drillers arrived.

- Todd Burnham, ATL to Spencer Thew, ATL at 12:30 p.m.

Todd is on-site and has met with Paul Hersom, USACE. Paul indicated that Tony Firicano would be on-site tomorrow at about 12:00 noon. Todd indicated that they would start platform construction for access to the bore holes at the toe of the dam.

Oct. 12, 1988 - Anthony (Tony) Firicano, USACE to Deanna Hadfield,
Wednesday ATL at 10:35 a.m.

Tony questioned the schedule of the drillers. His Project Manager called him earlier in the morning and said he has not seen anyone.

Deanna told Tony that as soon as she heard from someone, she would call him with status report.

- Jennie Mason, ATL to Anthony (Tony) Firicano, USACE at 2:14 p.m. Mr. Firicano was away from his desk. Left a message to please return the call.

- Anthony Firicano, USACE to Jennie Mason, ATL at 2:30 p.m. Jennie relayed a message to Mr. Firicano from Spencer Thew that we were waiting for a shipment of 6" casing to come in before we could begin drilling. We have ordered the casing to come as soon as possible. Mr. Firicano was told that the drillers would be on-site Monday morning. Mr. Firicano asked that the Inspector notify the Corps when they arrive on-site.

Oct. 17, 1988 - Spencer Thew, ATL to Ed Lippman, USACE, Assistant
Monday to the Project Manager at Birch Hill Dam at 8:00 a.m.

Spence indicated to him that the drillers would be on-site later this afternoon and that our Geotechnical Inspector would be there early this morning. Mr. Lippman indicated that he had already met the Geotechnical Inspector at about 6:30 a.m.

- Spencer Thew, ATL to Anthony Firicano, USACE at 8:00 a.m.

Anthony was not in so Spence talked to Tim Bouckman and asked Tim to relay the message to Tony that our Geotechnical Inspector was currently on-site and that our drillers would be on-site this afternoon and that we had mobilize the CME 850 to the site on Friday.

Oct. 18, 1988 - Chris Lawrence, ATL Geologist to Chris Alley
Tuesday USACE at 1 p.m.

Informed Chris Allie that we started drilling today as he wanted to visit the site. Chris Allie said he would visit the sight either Wednesday or Thursday of this week.

Anthony Firicano will be out of the office this week so Chris Allie is our daily contact at the Corps office.

Oct. 20, 1988 - Chris Lawrence, ATL Geologist to Chris Alley,
Thursday USACE at 2:30 p.m.

Chris informed Chris Alley of drilling progress - completed PZ-11 (FD-88-1) and PZ-10 (FD-88-2), filling the hole on PZ-15 (FD-88-3) and drilling only about 15' down on PZ-14 (FD-88-4). Mr. Alley instructed Chris that if we find yellowish sand and gravel as in PZ-10 (FD-88-2), we should move the upper piezometer down to a depth of one foot above the bottom of the yellowish layer. If the layer is less than 4 ft thick or non-existent, then follow the original diagram.

Oct. 24, 1988 - Spencer Thew, ATL to Yuri Yatsevitch, USACE at
Monday 8:30 a.m.

Spencer called Yuri and told him that we would be moving the CME 45 skid-rig to the dam site on Friday afternoon (10/28). We do not anticipate working Friday afternoon, however, would be set up to start Monday morning.

Spencer indicated that the work last week with the CME 75 and the CME 850 had gone more rapidly than anticipated. Spencer told Yuri that we had originally planned that the CME 75 and CME 850 would be completed on Wednesday, October 26, 1988. Once they were done, we could begin the slope holes with the CME 45. Yuri indicated that taking a week's break in the field would not create a problem as far as their schedule is concerned.

October 31, 1988 - Chris Lawrence, ATL Geologist to Tony Firicano,
Monday USACE at 8:30 a.m.

Chris Lawrence called Tony Firicano to inform him that our equipment should arrive on site today. The drill crew should begin setting up between 7 and 8 a.m. on Tuesday. This was acceptable.

If Tony Firicano is not in when the ATL representative places his daily progress report call, Terry Wong will be available.

November 1, 1988 - Chris Lawrence, ATL Geologist to Chris Alley,
Tuesday USACE at 1:00 p.m.

Chris Lawrence spoke with Chris Alley as Tony Firicano was not available today. ATL crew is on location and setting up equipment on first hole.

Chris Lawrence inquired if we could use NW casing instead of HW casing on the lower portion of the drill hole when only a single piezometer would be set? Chris Alley approved this but said to invoice accordingly. NW casing was not subsequently used.

November 2, 1988 - Chris Lawrence, ATL Geologist to Chris Alley,
Wednesday USACE at 2:30 p.m.

Chris Lawrence confirmed that the upper piezometer is being placed 2 ft above the base of the yellow-brown sand. Chris Allie was in agreement.

November 3, 1988 - Chris Lawrence, ATL Geologist to Terry Wong,
Thursday USACE at 1:30 p.m.

Chris Lawrence informed Terry Wong that we were drilling PZ-12 (FD-88-5) and had reached a depth of 16 ft; drilling had been slow because of rocks. Terry Wong will probably be on site Friday morning (November 4).

November 7, 1988 - Chris Lawrence, ATL Geologist to Terry Wong,
Monday USACE at 3 p.m.

Chris Lawrence, ATL, informed Terry Wong, USACE, that ATL's crew was on site and would be finishing the drilling, sampling and piezometer placement on PZ-12 (FD-88-5) Tuesday, November 8. Terry said fine.

November 8, 1988 - Chris Lawrence, ATL Geologist to Terry Wong,
Tuesday USACE at 12:30 p.m.

Chris Lawrence called to inform Terry Wong that we had reached the bottom of the hole. Also, that the yellow-brown sand and gravel that in which the upper piezometer is set, came in at 38 - 42 ft; there would not be enough room to set both piezometers and the bentonite seal as on the specs. Terry Wong said sample to 50 ft and wash the hole to 51 ft. Also, Tony Firicano, USACE, would be out at the site around 1:30 p.m. Chris said we would go back and drill the extra 2 ft.

November 9, 1988 - Chris Lawrence, ATL Geologist to Tony Firicano,
Wednesday USACE at 1:45 p.m.

Chris Lawrence informed Tony Firicano that we had completed PZ-12 (FD-88-5) and were moving the rig to PZ-13 (FD-88-6). Tony mentioned that he wanted the bentonite in the curb boxes reduced so when it expanded, it did not go into the piezometers.

November 10, 1988 - Chris Lawrence, ATL Geologist to Tony Firicano,
Thursday USACE at 2:15 p.m.

Chris told Tony we began drilling PZ-13 (FD-88-6) and have sampled 10 - 18 ft. At 18 ft, we hit a boulder and have been unable to collect the 18 - 20 ft sample. The 6" casing goes to a depth of 10 ft with the rest open hole 6" and we are now spinning the casing to 20 ft and will then try to drill through the rock.

Tony also said that if we get through the rock and do not see the yellow sand and gravel, simply follow the original diagram. Place the upper piezometer about one foot above the bottom of the sand and gravel. Also, because there is a 4 ft bentonite seal at the top of the silty sand, if we need to go deeper to get the proper spacing, do so.

Finally, because of Veterans Day, there will be no one to call Friday, November 11, 1988.

November 15, 1988 - Chris Lawrence, ATL Geologist to Tony Firicano,
Tuesday USACE at 8:20 a.m.

Chris Lawrence told Tony Firicano that we set the piezometers in PZ-13 (FD-88-6) on Friday and began dismantling the platform and moving the rig to PZ-16 (FD-88-7). Chris said they may be drilling by late this afternoon. Tony thought he might be on location Thursday. Also, if possible, he would like to see the site prior to the crew's departure next week.

November 16, 1988 - Chris Lawrence, ATL Geologist to Tony Firicano,
Wednesday USACE at 1:30 p.m.

Chris Lawrence told Tony Firicano that we moved the rig on Tuesday and began drilling Wednesday morning. Tony informed Chris that he would be on-site Thursday, midday.

November 18, 1988 - Chris Lawrence, ATL Geologist to Tony Firicano,
Friday USACE at 12:30 p.m.

Chris Lawrence informed Tony Firicano that we were moving the rig today but that because of the large rocks on the PZ-17 (FD-88-8) site, we would like to move the hole 5 ft to the left looking down from the road but keeping it at the same elevation. Tony saw no problem and approved the move. He also said that I did not have to call him during the weekend unless there is a problem.

SECTION 6

CHAIN OF CUSTODY LOG




atl

ATLANTIC TESTING LABORATORIES, Limited

CHAIN OF CUSTODY LOG FOR SOIL SAMPLES & ROCK CORES

Boring Logs: _____
Jar Samples: Birch Hill Dam
Rock Cores: _____
Tubes: _____

	<u>DATE & TIME OF TRANSFER</u>	<u>FROM</u>	<u>TO</u>	<u>LOCATION</u>	<u>SIGNATURE OF RECEIVER</u>
PZ10	<u>11/22 10 jars</u>	<u>Chris Lawrence</u>	<u>Tony Foricane</u>	<u>Birch Hill Dam</u>	
PZ11	<u>10 jars</u>	_____	_____	_____	
PZ12	<u>11 jars</u>	_____	_____	_____	
PZ13	<u>13 jars</u>	_____	_____	_____	
PZ14	<u>15 jars</u>	_____	_____	_____	
PZ15	<u>12 jars</u>	_____	_____	_____	_____



atl

ATLANTIC TESTING LABORATORIES, Limited

CHAIN OF CUSTODY LOG FOR SOIL SAMPLES & ROCK CORES

Boring Logs: _____
Jar Samples: Birch Hill Dam Project
Rock Cores: _____
Tubes: _____

DATE & TIME
OF TRANSFER

FROM

TO

LOCATION

SIGNATURE OF RECEIVER

P2-16 12 Jan

Chris Lawrence

Tim Farrisano

Birch Hill Dam

[Signature]

P2-17 11 Jan

SECTION 7
SAFETY REPORTS

WEEKLY SAFETY MEETING

NEDSO

Date held 10/18/87

TERU: Area Engineer, _____ Area

Time 6:45 AM

TO: Safety Office, NED

Report No. 1

1. Weekly safety meeting was held this date for the following personnel:

Contract No. /D.O.No. 033 Contractor Atlantic Testing Laboratories Ltd.Conducted By [Signature] All personnel present (Contr) 6 ATL
(Sub) _____
(Govt) _____Subjects discussed (Note, delete, or add):
EX 385-1-1, Section: _____

Accident Prevention Plan _____

Individual Protective Equipment - ☒Prevention of Falls ☒Back Injury, Safe Lifting Techniques - ☒Fire Prevention - ☒

Sanitation, First Aid, Waste Disposal _____

Tripping Hazards - trash, hose, nails in lumber _____

Staging, Ladders, Concrete Forms, Safety Nets - N/AHand Tools, Portable Power Tools, Woodworking Machinery - ☒Equipment Inspection & Maintenance (Zero Defects) - ☒Hoisting Equipment - ☒Ropes, Hooks, Chains and Slings - ☒Electrical Grounding, Temporary Wiring, GFCI - ☒Lockouts for safe clearance procedures - electrical, pressure, moving parts - ☒Welding, Cutting - N/AExcavations - ☒Loose Rock and Steep Slopes - ☒Explosives - N/AWater Safety - N/AToxic materials - hazards, MSDS, respiratory, ventilation - N/A

Other - _____

Prepared by _____ Title _____

2. Forwarded.

Signature [Signature]

Resident/Engineer

OF: EXPOSURE HOURS:

Work Date: _____

Non-work Date: _____

NED, 10/25/87

Man Hours:

Contr: 300

Subcontr: _____

Govt: _____

TOTAL: _____

WEEKLY SAFETY MEETING

Date held 11/7/98Time 5:00 - 5:30

NEDSO

FROM: Area Engineer, _____ Area

TO: Safety Office, NED

Report No. _____

1. Weekly safety meeting was held this date for the following personnel:

Contract No. /D.O.No. CP-033 Contractor Atlantic Testing Laboratories Ltd.Conducted By Chris Lawrence All personnel present (Contr) 3
(Sub) _____
(Govt) _____Subjects discussed (Note, delete, or add):
EM 385-1-1, Section: _____

Accident Prevention Plan _____

Individual Protective Equipment - _____

Prevention of Falls _____

Back Injury, Safe Lifting Techniques - _____

Fire Prevention - _____

Sanitation, First Aid, Waste Disposal _____

Tripping Hazards - trash, hose, nails in lumber _____

Staging, Ladders, Concrete Forms, Safety Nets - N/AHand Tools, Portable Power Tools, Woodworking Machinery - N/A

Equipment Inspection & Maintenance (Zero Defects) - _____

Hoisting Equipment - _____

Ropes, Hooks, Chains and Slings - _____

Electrical Grounding, Temporary Wiring, GFCI - N/ALockouts for safe clearance procedures - electrical, pressure, moving parts - N/AWelding, Cutting - N/AExcavations - N/A

Loose Rock and Steep Slopes - _____

Explosives - N/AWater Safety - N/AToxic materials - hazards, MSDS, respiratory, ventilation - N/A

Other - _____

Prepared by Chris Lawrence Title Geologist

Signature _____

Resident/Engineer

2. Forwarded.

EXP: EXPOSURE HOURS:

Work Date: _____

Non-work Date: _____

NED, 11/7/98

Man Hours:

Contr: 120

Subcontr: _____

Govt: _____

TOTAL: _____

NEDSO

WEEKLY SAFETY MEETING

Date held 11/14/88

Time 6:30 - 7:00 P.M.

FROM: Area Engineer, Tampa Electric Area

TO: Safety Office, NED

Report No. _____

1. Weekly safety meeting was held this date for the following personnel:

Contract No. 1D.O.No. CD-033 Contractor Atlantic Testing Laboratories Ltd.

Conducted By Chris Lawrence All personnel present (Contr) 3
(Sub) _____
(Govt) _____

Subjects discussed (Note, delete, or add):

EM 385-1-1, Section: _____

Accident Prevention Plan _____

Individual Protective Equipment - ☒

Prevention of Falls - ☒

Back Injury, Safe Lifting Techniques - ☒

Fire Prevention - N/A

Sanitation, First Aid, Waste Disposal - ☒

Tripping Hazards - trash, hose, nails in lumber - ☒

Staging, Ladders, Concrete Forms, Safety Nets - N/A

Hand Tools, Portable Power Tools, Woodworking Machinery - N/A

Equipment Inspection & Maintenance (Zero Defects) - ☒

Hoisting Equipment - ☒

Ropes, Hooks, Chains and Slings - ☒

Electrical Grounding, Temporary Wiring, GFCI - N/A

Lockouts for safe clearance procedures - electrical, pressure, moving parts - ☒

Welding, Cutting - N/A

Excavations - N/A

Loose Rock and Steep Slopes - ☒

Explosives - N/A

Water Safety - N/A

Toxic materials - hazards, MSDS, respiratory, ventilation - N/A

Other -

Prepared by Chris Lawrence Title Geologist

2. Forwarded.

Signature Chris Lawrence
Resident Engineer

3. EXPOSURE HOURS:

Work Date: _____

Non-work Date: _____

NO. 251

Man Hours:

Contr: 198

Subcontr: _____

Govt: _____

TOTAL: _____

WEEKLY SAFETY MEETING

NEDSO

Date held 11/21/82FROM: Area Engineer, Tony Farina AreaTime 6:30

TO: Safety Office, NED

Report No. _____

1. Weekly safety meeting was held this date for the following personnel:

Contract No. /D.O.No. CD-037 Contractor Atlantic Testing Laboratories, Ltd.Conducted By Chris Lawrence All personnel present (Contr) 3
(Sub) _____
(Govt) _____Subjects discussed (Note, delete, or add):
EM 385-1-1, Section: _____

Accident Prevention Plan - ✓

Individual Protective Equipment - ✓

Prevention of Falls - ✓

Back Injury, Safe Lifting Techniques - ✓

Fire Prevention - N/A

Sanitation, First Aid, Waste Disposal - ✓

Tripping Hazards - trash, hose, nails in lumber - ✓

Staging, Ladders, Concrete Forms, Safety Nets - N/AHand Tools, Portable Power Tools, Woodworking Machinery - N/A

Equipment Inspection & Maintenance (Zero Defects) - ✓

Hoisting Equipment - ✓

Ropes, Hooks, Chains and Slings - ✓

Electrical Grounding, Temporary Wiring, GFCI - N/A

Lockouts for safe clearance procedures - electrical, pressure, moving parts - ✓

Welding, Cutting - N/AExcavations - N/A

Loose Rock and Steep Slopes - ✓

Explosives - N/AWater Safety - N/AToxic materials - hazards, MSDS, respiratory, ventilation - N/A

Other -

Prepared by Chris Lawrence Title Geologist

2. Forwarded.

Signature Chris Lawrence

Resident Engineer

OF: EXPOSURE HOURS:

Work Date: _____

Non-work Date: _____

110,000 251

Man Hours:

Contr: 75

Subcontr: _____

Govt: _____

TOTAL: _____

SECTION 8

FIELD INSPECTOR'S LOGS

CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site Bird Hill Dam PROJECT NO. CD-073
Page 1 of 9 Pages
Hole No. P2-1 Diam. (Casing) 6" SW Boring Started 10/12/88
FD-88-1
Co-ordinates: N 594922 E 432140 Boring Completed 10/19/88
Drilled by Hawkins - MacLean Report Submitted 12/21/88
Purpose of Exploration Install 2 piezometers.

Elevation Top of Hole 244' M.S.L. Casing Left In Place FLUSH MOUNTED CASE Foot
Total Overburden Drilled 64' Foot Box
Elevation Top of Rock _____ M.S.L.
Elevation Bottom of Hole 200 M.S.L.
Total Rock Drilled _____ Foot
Total Depth of Hole 64' Foot
Core Recovered _____ %
Core Recovered _____ Ft.; _____ Dia. _____ In.
Soil Samples 1 3/4' In. Dia. 10 No.
Soil Samples _____ In. Dia. _____ No. Water Table Depth ≈ 47'

Depth		Method of Drilling and Type of Bit Used
From	To	
0	54'	Entire hole drilled with 6" SW Casing
0	14'	No samples as per instructions
44	64	Continuous sampling
44	51	Lower piezometer (orange)
61	63	Lower piezometer (grey)

INDEX	
Ground Water	Back of Page <u>5</u>
Boring Location Sketch	Back of Page <u>5</u>
Overburden Record	Page <u>2-6</u>
Rock Drilling	Page _____
Piezometer Installation Report	Page <u>7</u>
"	DETAIL Page <u>8</u>
"	Page _____

Prepared by Christopher H. Lawrence
Field Data

Submitted by ATMATIC TESTING LABORATORIES
Lab. Data

Site

Birch Hill Dam

Boring No.

PZ-11 FD-88-1

Page

of 9

DEPTH		CORE/SAMPLE			BLOWS PER FT. CORE REC'D	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
	IN	NO.	SIZE	DEPTH RANGE			
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							
22							
23							
24							
25							
26							
27							

Site <i>Buck Hill Dam</i>					Boring No. <i>PZ-11 FD-88-1</i>		Page <i>9</i> of <i>9</i>	
DEPTH		CORE/SAMPLE		BLOWS PER FT. CORE RECVY	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS		
IN.	NO.	SIZE	DEPTH RANGE					
27								
28								
29								
30								
31								
32								
33								
34								
35								
36								
37								
38								
39								
40								
41								
42								
43								

Site					Boring No.		Page <u>5</u>	
Birken Hill Dam					PZ-11 FL-88-1		of <u>9</u>	
DEPTH		CORE/SAMPLE		BLOWS PER FT.	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS		
	ft.	NO.	SIZE	DEPTH RANGE			CORE RECVY	
43								
44								
45		S-1	1 3/8"	80%	20 21 24 37	Started sampling, 1 3/8" I.D. spoon with 140 lbs hammer dropping 30" Brown, mf, SAND Little, cmf, GRAVEL Trace, SILT(np) SP-SM		
46					23	Sampled — WATER TABLE @ 47'		
47		S-2	1 3/8"	90%	95 37 15			
48					11			
49		S-3	1 3/8"	90%	25 19 16	Sampled Augered to 52', Similar Soil		
50					15	Sampled Similar Soil		
51		S-4	1 3/8"	100%	23 48 59			
52					13			
53		S-5	1 3/8"	100%	25 27 20	Sampled Augered to 56' Lt. Gray, mf, SAND Trace, SILT(np) Trace, mf, GRAVEL SP-SM		
54					11	Sampled Similar Soil		
55		S-6	1 3/8"	100%	20 21 20			
56					14			
57		S-7	1 3/8"	90%	13 12 22	Sampled Augered to 58' Similar Soil Sample very wet		
58					24	Sampled Similar Soil		
59		S-8	1 3/8"	100%	29 40 39			
60								

Site					Boring No.		Page	
Birch Hill Dam					PZ-11 FD-88-1		6 of 9	
DEPTH	F.T.	CORE/SAMPLE		BLOWS PER FT. CORE RECVY	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS		
		NO.	SIZE					
60				4	Sampled Augered to 64'	Similar Soil		
61		S-9	1 3/8"	4 8 8				
62				3				
63		S-10	1 3/8"	8 12 13				
64					Bottom of hole.	Similar Soil		
					10/18/88 - Drilling, sampling, and running 6" casing completed. 10/19/88 - Set upper piezom- eter at 51' and lower piezometer at 63'. 11/20/88 - Curb box was cemented into place.			

PIEZOMETER INSTALLATION REPORT

page 7 of 9

PROJECT: Red D. DATE: 11/14/52
 LOCATION (STA): PZ 11 STA 7400 OFFSET FROM CENTER LINE: on C PIEZ NO.: P7
 PIEZ TYPE: Caso Grande DEPTH upper 51' RISER PIPE 3/4"
 OF PIEZ: Lower 63' DIAM:
 PIEZ TIP SET IN upper SP-SM SOIL S-4
 (SOIL TYPE): Lower SP-SM SAMPLE NO.: S-10 BORING DIAM: 6"

METHOD OF INSTALLATION:

TYPE OF PROTECTION

FOR PIEZ: Curb box in Roadway

VENT:

GROUND ELEV.: 864.26 ELEV. TOP upper 863.76 ELEV 813.3
 OF RISER: Lower 864.01 PIEZ TIP: 801.3

FILTER: #4 Sand FROM ELEV: upper 812.3 TO ELEV: 818.3
Lower 800.3

SEAL: Bentonite Pellets FROM ELEV: upper 852.3 TO ELEV: 856.3
Lower 808.3

INSTALLED BY: Hawkins + McAlcon CONTRACT NO.: 0008 FOREMAN: Paul Davis

DATE OF INSTALLATION: 10/19/52 DATE OF OBSERVATIONS: 11/14/52

METHOD OF

TESTING PIEZ.: Falling Head Test

TIME	ELAPSED TIME MINUTES	DEPTH TO WATER FEET	TIME	ELAPSED TIME MINUTES	DEPTH TO WATER FEET	TIME	ELAPSED TIME MINUTES	DEPTH TO WATER FEET
	0	* 0		0	** 0			
	1	45'		1	45'			
	2	45 1/2'		2	46 1/2'			
	5	45 1/2'		4	47'			
	10	47'		10	47'			

REMARKS:

* WATER AT 47' PRIOR TO TESTING

** WATER AT 47' PRIOR TO TESTING

Christopher H. Lawrence
 INSPECTOR


Site: Brick 4th Dam
Boring No: B2-11

SUBSURFACE WATER OBSERVATIONS

DATE	TIME	DEPTH-BOT. OF CASING	DEPTH-BOT. OF BORING	DEPTH TO WATER		ELEVATION WATER		REMARKS
				Upper	Lower	Upper	Lower	
								ST 3/13/33
10/21	11:00		64	12'	10'	852	854	
11/6			64	17	47 1/3	847	846 2/3	
11/16	1:30		64	45'	46 1/2	819	817 1/2	
11/14			64	47'	48	817	817	Falling Head Test
11/17			64	46	45	818	818	
11/19			64	47'	45 1/2	817	818 1/2	
11/21			64	47	45	817	818	
12/15	Noon			47.0	47.5	817.3	816.5	STATIC

Note: Depths are in feet below original ground

BORING LOCATION SKETCH



Casagrande Piezometer

CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site Barn Hill Dam PROJECT NO. CD-033
 Hole No. PZ 10 Diam. (Casing) 6" SW Page 1 of 8 Pages
FL-88-2
 Co-ordinates: N 594919 E 432181 Boring Started 10/13/58
 Drilled by Burnham + Hart Boring Completed 10/19/58
 Report Submitted 12/21/58
 Purpose of Exploration Piezometer Installation

Elevation Top of Hole 855 M.S.L. Casing Left in Place 4" DIA - 10 Feet
 Total Overburden Drilled 56 Feet
 Elevation Top of Rock _____ M.S.L.
 Elevation Bottom of Hole 799 M.S.L.
 Total Rock Drilled _____ Feet
 Total Depth of Hole 556 Feet
 Core Recovered _____ %
 Core Recovered _____ Ft.; _____ Dia. _____ In.
 Soil Samples 1 1/2 I.D. In. Dia. 10 No.
 Soil Samples _____ In. Dia. _____ No.
 Water Table Depth 37'

Depth		Method of Drilling and Type of Bit Used	INDEX
From	To		
0	56	Spun 6" SW flush coupled casing	Ground Water _____ Back of Page <u>7</u>
0	35	No samples as per instructions	Boring Location Sketch _____ Back of Page <u>7</u>
35	55	Continuous Sampling	Overburden Record <u>pages 2-5</u> Page _____
44	46	Piezometer (orange)	Rock Drilling _____ Page _____
53	55	Piezometer (grey)	Piezometer Installation Report Page <u>6</u>
			" " DETAIL Page <u>8</u>
			Page _____

Prepared by Christopher H. Lawrence Field Data
 Submitted by ATLANTIC TESTING LABORATORIES Lab. Data

U. S. ARMY
CORPS OF ENGINEERS
NEW ENGLAND DIVISION

Site Birch Hill Dam Page 2 of 8 Pages

Boring No. P2-10 Desig. _____ Diam. (Casing) 6"

FIELD LOG OF TEST BORING

Co-ordinates: N 594918 E 432181

Elevation Top of Boring 855' M.S.L. Hammer Wt. 140 Boring Started 10/12/55
Total Overburden Drilled 76' Feet Hammer Drop 30"
Elevation Top of Rock _____ M.S.L. Casing Left 10' Boring Completed 10/19/55
Total Rock Drilled _____ Feet Subsurface Water Data _____ Page 7
Elevation Bottom of Boring 799' M.S.L. Obs. Well Piez
Total Depth of Boring 56' Feet Drilled By Burnham + Hart
Core Recovered _____ % No. Boxes _____ Mfg. Des. Drill _____
Core Recovered _____ Ft : _____ Diam. _____ In. Inspected By: Christopher H. Lawrence
Soil Samples 1 3/4 T.D. In. Diam. 10 No. Classification By: Christopher H. Lawrence
Soil Samples _____ In. Diam. _____ No. Classification By: _____

DEPTH		CORE/SAMPLE			BLOWS PER FT. CORE REC'Y	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
	ft.	NO.	SIZE	DEPTH RANGE			
0						Spun SW flash coupled 6" casing to 56'.	
1							
2							
3							
4							
5							
6							
7							
8							
9							
10							

GENERAL REMARKS:

DEPTH		CORE/SAMPLE			BLOWB PER FT. CORE REC'Y	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
	ft.	NO.	SIZE	DEPTH RANGE			
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							
22							
23							
24							
25							
26							
27							

DEPTH	CORE/SAMPLE			BLOWS PER FT. CORE RECVY	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
	NO.	SIZE	DEPTH RANGE			
28						
29						
30						
31						
32						
33						
34						
35				12	Sampled with 1 3/8" I.D. Spoon with 140 lbs hammer	Lt. Gray, mf, SAND; Trace, cmf, ROCK FRAG., Trace, SILT, (np) SP-SM
36	S-1	1 3/8"	90%	29		
				23		
37				31		
38				23	Sample Spun 6" casing to 39' and washed to 39' with th 5 7/8" roller bit and water	Lt. Brn, mf, SAND; Little, F, GRAVEL; Trace, SILT (np) SP-SM
39	S-2	1 3/8"	80%	22		
				24		
				15		
40				27	Sample Spun 6" casing to 43' and washed to 43' with 5 7/8" roller bit and water	Lt Brn, mf, SAND; Little, F, GRAVEL, Trace, SILT (np) SP-SM
41	S-3	1 3/8"	90%	35		
				36		
				20		
42				31	Sample Spun 6" casing to 43' and washed to 43' with 5 7/8" roller bit and water	Similar Soils SP-SM
43	S-4	1 3/8"	60%	20		
				24		
				51		
44				42	Sample	Brown, c-mf, SAND. Trace, m, GRAVEL SP-SM
45	S-5	1 3/8"	70%	109		
				85		
				62		

Site					Boring No.		Page <u>5</u> of <u>8</u>	
Birch Hill Dam					PZ-10 FD-88-2			
DEPTH		CORE/SAMPLE		BLOWS PER FT.	SAMPLING AND CORING OPERATIONS		CLASSIFICATION OF MATERIALS	
	ft.	NO.	SIZE	DEPTH RANGE	CORE RECOVERY			
45					19	Sample		Similar Soil
46		S-6	1 3/8"	70%	52 72 60			SP-SM
47					13	Sample		Brown, c-mf, SAND
48		S-7	1 3/8"	70%	18 21 23	Spun 6" casing to 47' and washed to 47' with 5 3/8" roller bit and water		Lt. Grey, SILT Trace, f, SAND Trace, CLAY ^{Very Slightly Plastic} ML
49					20	Sample		Lt. Grey, SILT
50		S-8	1 3/8"	60%	30 23 32			Trace, f, SAND Trace, CLAY - ML
51					47	Sample		Similar Soil
52		S-9	1 3/8"	70%	22 21 18	Spun casing to 51' and washed hole to 51' with 5 3/8" roller bit and water		
53					39	Sample		Similar Soil
54		S-10	1 3/8"	60%	57 41 16			
55								
56						Hole was washed to a depth of 56' with 5 3/8" roller bit and water. Drilling Ended 10/19/88 10/18/88 - Completed drilling and sampling 10/19/88 Set upper piezometer at 46 (orange) Lower piezometer 55 (grey)		

PIEZOMETER INSTALLATION REPORT

PROJECT: *Burnham Hill Dr.*DATE: *11/9/88*LOCATION (STA): *P2-12* STA. 7+00 CENTER LINE: *35' Rt.* PIEZ NO.: *PE-12*PIEZ TYPE: *Casagrande* DEPTH *Upper 46'* RISER PIPE *3/4"*
OF PIEZ: *Lower 55'* DIAM:PIEZ TIP SET IN *SP-SM* SOIL *S-6*
(SOIL TYPE): *ML* SAMPLE NO.: *S-10* BORING DIAM: *6"*

METHOD OF INSTALLATION:

TYPE OF PROTECTION

FOR PIEZ: *4" Protective Pipe* VENT: *Screw on Cap*GROUND ELEV.: *854.9* ELEV. TOP *Upper 858.0* ELEV *810.9*
OF RISER: *Lower 858.1* PIEZ TIP: *799.9*FILTER: *#4 Sand* FROM ELEV: *Upper 805.9* TO ELEV: *846.9*
*Lower 798.9*SEAL: *Bentonite Pellets* FROM ELEV: *Upper 846.9* TO ELEV: *850.9*
*Lower 803.9*INSTALLED BY: *Burnham + Hart* CONTRACT NO.: *CC08* FOREMAN: *Paul Davis*DATE OF INSTALLATION: *10/17/88*DATE OF OBSERVATIONS: *11/9/88*

METHOD OF

TESTING PIEZ.: *Falling Head Test*

TIME	ELAPSED TIME MINUTES	DEPTH TO WATER FEET	TIME	ELAPSED TIME MINUTES	DEPTH TO WATER FEET	TIME	ELAPSED TIME MINUTES	DEPTH TO WATER FEET
	<i>1</i>	<i>* 0</i>		<i>1</i>	<i>** 0</i>			
	<i>1</i>	<i>31</i>		<i>1</i>	<i>29</i>			
	<i>2</i>	<i>33</i>		<i>2</i>	<i>34</i>			
	<i>4</i>	<i>39</i>		<i>4</i>	<i>39</i>			
	<i>10</i>	<i>39</i>		<i>10</i>	<i>39 1/3</i>			

REMARKS:


** WATER AT 39' PRIOR TO TESTING**** WATER AT 39 1/3' PRIOR TO TESTING*

Christopher H. Lawrence
INSPECTOR

Site: <u>B. L. 4.30 Dam</u> Boring No: <u>PZ-10</u>	SUBSURFACE WATER OBSERVATIONS
--	--------------------------------------

DATE	TIME	DEPTH-BOT. OF CASING	DEPTH-BOT. OF BORING	DEPTH TO WATER		ELEVATION WATER		REMARKS
				Upper	Lower	Upper	Lower	
10/21			56	37 1/8	40	817 1/2	815	
11/9			56	39 1/3	39	815 1/3	816	Falling Head Tests.
11/10	1100		56	41	41	814	814	
11/13			56	42	40 1/2	813	814 1/2	
11/14			56	40	40	815	815	
11/15			56	39	40	816	815	
11/16			56	38	39	817	816	
11/17			56	39	40	816	815	
11/18			56	39	39	816	816	
12/15	1700			40.2	40.5	817.8	817.6	STATIC

Note: Depths are in feet below original ground.



ATLANTIC TESTING LABORATORIES, LIMITED

al

PIEZOMETER INSTALLATION DETAIL

PROJECT Birch Hill Dam, Ma.

CONTRACT No. DACW-33-87-D-0007

CLIENT U.S. Army Corps of Engineers
Waltham, Massachusetts

ATL PROJECT No. CD033

PIEZOMETER No. PZ-10

Orange Paint

TOP PROTECTIVE PIPE 858.11
TOP LOWER PIEZOMETER RISER 858.07
TOP UPPER PIEZOMETER 857.99

1/2" PVC Sch 80
Riser Pipe

Sagrande
Piezometer

Sagrande
Piezometer

SURFACE ELEVATION	854.9'	DEPTH	SOIL STRATA
Surface Gravel	850.9'	4'	No samples as per instructions.
Bottom of Pipe	848.1'	7'	
Bentonite Seal	846.1'	9'	
		35'	
Filter Sand			Light grey brown mf SAND, little GRAVEL and ROCK FRAGMENTS, trace SILT (non-plastic) SP - SM
Water Table	817.6'	37.3'	
Tip of Piezometer	810.9'	44'	
		43'	
		47'	Brown cmf SAND, trace m GRAVEL (non-plastic) SP - SM
		49'	Brown c-mf SAND, light grey SILT, trace SAND, trace CLAY (very slightly plastic) ML
Bentonite Seal	803.9'	51'	Light grey SILT, trace f SAND, trace clay (very slightly plastic) ML
Filter Sand			
Tip of Piezometer	799.9'	55'	
Bottom	798.9'	56'	

CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site Birch Hill Dam PROJECT NO. CD-033
Page 1 of 9 Pages
Hole No. P2-15 Diam. (Casing) 6" SW Boring Started 10/19/88
FD-88-3
Co-ordinates: N 594574 E 432106 Boring Completed 10/20/88
Drilled by Hawkins + McAlister Report Submitted 12/21/88
Purpose of Exploration Install 2 piezometers

Elevation Top of Hole 864 M.S.L. Casing Left in Place FLUSH MOUNTED CONCRETE Feet
Total Overburden Drilled 65 Feet Box
Elevation Top of Rock _____ M.S.L.
Elevation Bottom of Hole 799 M.S.L.
Total Rock Drilled _____ Feet
Total Depth of Hole 65' Feet
Core Recovered _____ %
Core Recovered _____ Ft.; _____ Dia. _____ In.
Soil Samples 1 3/8" I.D. In. Dia. 12 No.
Soil Samples _____ In. Dia. _____ No. Water Table Depth 51'

Depth		Method of Drilling and Type of Bit Used
From	To	
0	65	Entire hole drilled with 6" SW Casing
0	40	No samples as per instructions
40	64	Continuous sampling
45	47	Upper Piezometer (orange)
62	64	Lower Piezometer (gray)

INDEX	
Ground Water	Back of Page <u>8</u>
Boring Location Sketch	Back of Page <u>8</u>
Overburden Record	pages <u>2 - 6</u> Page _____
Rock Drilling	Page _____
Piezometer Installation REPORT	Page <u>7</u>
" " " " " "	DETAIL Page <u>9</u>
" " " " " "	Page _____

Prepared by Christopher H. Lawrence Field Data
Submitted by ATLANTIC TESTING LABORATORIES Lab. Data

U. S. ARMY
CORPS OF ENGINEERS
NEW ENGLAND DIVISION

Site Birch Hill Dam Page 2 of 9 Pages

Boring No. P2-15 Desig. _____ Diam. (Casing) 6"

FD-88-3

Co-ordinates: N 594574 E 432106

FIELD LOG OF TEST BORING

Elevation Top of Boring 864' M.S.L. Hammer Wt. 140 Boring Started 10/19/22
Total Overburden Drilled 65 Feet Hammer Drop 30" Boring Completed 10/20/22
Elevation Top of Rock _____ M.S.L. Casing Left _____
Total Rock Drilled _____ Feet | Subsurface Water Data _____ Page 8
Elevation Bottom of Boring 799 M.S.L. Obs. Well _____
Total Depth of Boring 65 Feet Drilled By Hawkins + McAlcon
Core Recovered _____ % No. Boxes _____ Mfg. Des. Drill _____
Core Recovered _____ Ft : _____ Diam. _____ In. Inspected By: Christopher H. Lawrence
Soil Samples 1 3/8" In. Diam. 12 No. Classification By: Christopher H. Lawrence
Soil Samples _____ In. Diam. _____ No. Classification By: _____

DEPTH		CORE/SAMPLE			BLOWS PER FT. CORE REC'Y	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
	ft.	NO.	SIZE	DEPTH RANGE			
0						Entire hole drilled with 4 1/4" auger with the 6" SW Flush coupled casing advanced with 300 lbs hammer to 62 1/2 feet.	No samples taken to a depth of 40' as per instructions.
1							
2							
3							
4							
5							
6							
7							
8							
9							
10							

GENERAL REMARKS:

Site <u>Birch Hill Dam</u>	Boring No. <u>PZ-15 FD-88-3</u>	Page <u>2</u> of <u>9</u>
-------------------------------	------------------------------------	------------------------------

DEPTH		CORE/SAMPLE		BLOWS PER FT.	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
	IN	NO.	SIZE	DEPTH RANGE		
10						
11						
12						
13						
14						
15						
16						
17						
18						
19						
20						
21						
22						
23						
24						
25						
26						
27						

Site					Boring No.		Page	
Barron Hill Dam					PZ-15 FD-88-3		2 of 9	
DEPTH		CORE/SAMPLE		BLOWS PER FT. CORE RECVY	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS		
IN	NO.	SIZE	DEPTH RANGE					
27								
28								
29								
30								
31								
32								
33								
34								
35								
36								
37								
38								
39								
40								
41		S-1	1 3/8"	70%	39 48 37 25	Sampled with 1 3/8" I.D. Spoon advanced with the 140 lbs hammer.	Brown, mf, SAND Trace, SILT. Trace, ROCK FRAGMENTS (np) Dry SP-SM	
42					15			
43		S-2	1 3/8"	90%	37 49	Similar Soil Little, mf, GRAVEL SP-SM (np) Dry		
44					50			

Site					Boring No.		Page
Burr Hill Dam					PZ-15 FD-88-3		5
DEPTH		CORE/SAMPLE		BLOWS PER FT.	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS	
	ft.	NO.	SIZE	DEPTH RANGE			CORE RECVY
44					32	Sample - Augered down to 42'	Same Soil Dry SP-SM
45		S-3	1 3/8"	90%	75		
	37						
	34						
46					27	Sample	Brown + Dark Grey, mf, SAND Trace, GRAVEL, Trace S.- (np) Dry. SP-SM
47		S-4	1 3/8"	100%	38		
	78						
	53						
48					49	Sample Augered down to 52'	Same Soil Little, GRAVEL (np) Dry SP-SM
49		S-5	1 3/8"	100%	57		
	45						
	49						
50					13	Sampled	Lt Grey + Brown, mf, SAND, Trace, SILT (np) Wet SP-SM
51		S-6	1 3/8"	90%	18		
	17						
	18						
52					15	Sampled Augered to 56'	Lt. Brown, mf, SAND Trace, SILT (np) Wet SP-SM
53		S-7	1 3/8"	90%	17		
	15						
	15						
54					3	Sample	Lt. Grey, f, SAND Little, SILT (np) Wet SP-SM
55		S-8	1 3/8"	100%	5		
	5						
	6						
56					7	Sample Augered to 60'	Lt Grey, SILT, some, SAND Lt Grey, some, CLAY (usp) Wet SP-SC
57		S-9	1 3/8"	100%	8		
	6						
	6						
58					4	Sample	Similar Soil (usp) Wet SP-SC
59		S-10	1 3/8"	100%	3		
	6						
	15						
60					6	Sample Augered to 64'	Similar Soil (usp) Wet SP-SC
61		S-11	1 3/8"	90%	8		

Site					Boring No.		Page	
Birch Hill Dam					PZ-15 FD-88-3		6 of 9	
DEPTH		CORE/SAMPLE		BLOWS PER FT. CORE RECVY	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS		
IN	NO.	SIZE	DEPTH RANGE					
61		S-11		7	<p>Sample</p> <p>Advanced 6" sus casing with 300 lbs hammer to a depth of 62 1/2'.</p>	<p>Similar Soil (USP) Wet SP-SC</p>		
62				7				
63		S-12	1 3/8"	6				
			90%	8				
				10				
64				11	Augered to 65'			
65					<p>10/19/88 - Completed drilling, sampling, and running casing.</p> <p>10/20/88 - set upper piezometer at 47 (orange)</p> <p>Lower piezometer at 64.</p> <p>Curb box put in.</p>			

PIEZOMETER INSTALLATION REPORT

PROJECT: Bird Hill DamDATE: 11/1/88LOCATION (STA): P-15 Sta 10+50 OFFSET FROM CENTER LINE: on ϕ PIEZ NO.: PZ-15PIEZ TYPE: Casagrande DEPTH Upper 45-47 RISER PIPE 3/4"
OF PIEZ: Lower 62-64 DIAM:PIEZ TIP SET IN Upper SP-SM SOIL S-3 + S-4
(SOIL TYPE): Lower SP-SC SAMPLE NO.: S-12 BORING DIAM: 6"

METHOD OF INSTALLATION:

TYPE OF PROTECTION

FOR PIEZ: Curb Box in Roadway VENT: Screw on CapGROUND ELEV.: 864.5 ELEV. TOP Upper 864.33 ELEV Upper 817.5
OF RISER: Lower 864.33 PIEZ TIP: Lower 800.5FILTER: #4 Sand FROM ELEV: Upper 816.5 TO ELEV: 825.0
Lower 799.5 812.5SEAL: Bentonite Pellets FROM ELEV: Upper 858.5 TO ELEV: 862.5
Lower 812.5 816.5INSTALLED BY: Haukins and McAlcon CONTRACT NO.: 0008 FOREMAN: Paul DavisDATE OF INSTALLATION: 10/20/88DATE OF OBSERVATIONS: 11/14/88

METHOD OF

TESTING PIEZ.: Falling Head (F.H.)

TIME	ELAPSED TIME MINUTES	DEPTH TO WATER FEET	TIME	ELAPSED TIME MINUTES	DEPTH TO WATER FEET	TIME	ELAPSED TIME MINUTES	DEPTH TO WATER FEET
	0	* 0'		0	0'		15	34 1/2'
	1	46'		1	32'		30	35 1/2'
	2	47'		2	33'			
	3	48'		4	33'			
	10	48'		10	33 3/4'			

REMARKS:


* WATER AT 48' PRIOR TO TESTING

** WATER AT 36' PRIOR TO TESTING

Christopher H. Lawrence
INSPECTOR

Site: <u>St. Louis Dam</u>		SUBSURFACE WATER OBSERVATIONS				
Boring No: <u>PZ-15</u>						
DATE	TIME	DEPTH-BOT. OF CASING	DEPTH-BOT. OF BORING	DEPTH TO WATER	ELEVATION WATER	REMARKS
				Upper Lower	Upper Lower	
11/9				16 18	248 845	
11/10	2:00			35 1/2 53 1/2	225 2/3 810 1/3	
11/14	10:00			36 48	226 812	Falling Head Test
11/15				37 55 1/2	227 211 1/2	
11/17	9:00			38 52	227 812	
11/19	10:00			37 52	227 812	
11/21	11:00			36 51	228 211	
12/5	12:00			37 6 46 4	826.7 817.9	STATIC

Note: Depths are in feet below original ground



ATLANTIC TESTING LABORATORIES, LIMITED

at

PIEZOMETER INSTALLATION DETAIL

PROJECT Birch Hill Dam, Ma.

CONTRACT No. DACW-33-87-D-0007

ATL PROJECT No. CD033

CLIENT U.S. Army Corps of Engineers
Waltham, Massachusetts

PIEZOMETER No. PZ-15

TOP Flush Valve Box 864.48

TOP LOWER PIEZOMETER RISER 864.33

TOP UPPER PIEZOMETER 864.33

Orange
Paint

See Detail

4" PVC Sch 80
Riser Pipe

Casagrande
Piezometer

Casagrande
Piezometer

SURFACE
ELEVATION 864.5' DEPTH

Concrete 864.0' 0.5'

Sand 860.5 4.0'

Bentonite Seal 858.5' 6'

Backfill

Water Table ∇ 826.7' 37.6'

825.0' 39.5'

40'

Filter Sand

Water Table ∇ 817.9' 46.4'

Tip of Piezometer 817.5' 47'

816.5' 48'

Bentonite Seal

50'

812.5' 52'

56'


Filter Sand

Tip of Piezometer 800.5' 64'

Bottom 799.5' 65'

SOIL STRATA

No samples above 40' as per instructions.



Brown and grey mf SAND, trace GRAVEL, trace SILT (non-plastic) SP - SM

Light grey f SAND, little SILT (non-plastic) SP - SM

Light grey SILT, some SAND, light grey, some CLAY (very slightly plastic) SP-SC

CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site Birch Hill Dam PROJECT NO. CD-033
Page 1 of 8 Pages
Hole No. 22-14 Diam. (Casing) 6" SW Boring Started 10/20/88
FD-88.4
Co-ordinates: N 594572 E 432148 Boring Completed 10/21/88
Drilled by BURHAM & HART Report Submitted 12/21/88

Purpose of Exploration Install 2 piezometers

Elevation Top of Hole 854 M.S.L. Casing Left in Place 4" DIA. - 10' Feet
Total Overburden Drilled 56 Feet
Elevation Top of Rock _____ M.S.L.
Elevation Bottom of Hole 798 M.S.L.
Total Rock Drilled _____ Feet
Total Depth of Hole 56 Feet
Core Recovered _____ %
Core Recovered _____ Ft.; _____ Dia. _____ In.
Soil Samples 1 3/8" I.D. In. Dia. 13 No.
Soil Samples _____ In. Dia. _____ No. Water Table Depth 36'

Depth		Method of Drilling and Type of Bit Used
From	To	
0	56	Spur 6" Flush coupled casing
0	29	No samples as per instructions
29	56	Continuous samples
40	42	Upper Piezometer (orange)
53	55	Lower Piezometer (gray)

INDEX	
Ground Water _____	Back of Page <u>1</u>
Boring Location Sketch _____	Back of Page <u>7</u>
Overburden Record <u>pages 2-5</u>	Page _____
Rock Drilling _____	Page _____
<u>Piezometer Installation Report</u>	Page <u>6</u>
" " <u>DETAIL</u>	Page <u>7</u>
_____	Page _____

Prepared by Christopher H. Lawrence
Field Data
Submitted by ATLANTIC TESTING LABORATORIES

Lab. Data _____

U. S. ARMY
CORPS OF ENGINEERS
NEW ENGLAND DIVISION

Site Birch Hill Dam Page 2 of 8 Pages

Boring No. PZ-14 Desig. _____ Diam. (Casing) 6"
FD-88-4

FIELD LOG OF TEST BORING

Co-ordinates: N 594572 E 432148

Elevation Top of Boring 254 M.S.L. Hammer Wt. 140 lbs Boring Started 10/20/88
Total Overburden Drilled 56 Feet Hammer Drop 30"
Elevation Top of Rock _____ M.S.L. Casing Left 10' Boring Completed 10/21/88
Total Rock Drilled _____ Feet | Subsurface Water Data _____ Page 7
Elevation Bottom of Boring 298 M.S.L. | Obs. Well _____
Total Depth of Boring 56 Feet | Drilled By Burnham + Hart
Core Recovered _____ % No. Boxes _____ Mfg. Cos. Drill _____
Core Recovered _____ Ft : _____ Diam. _____ In. | Inspected By: Christopher H. Lawrence
Soil Samples 1 3/8" I.D. In. Diam. 11 No. | Classification By: Christopher H. Lawrence
Soil Samples 2 3/8" I.D. In. Diam. 2 No. | Classification By: _____

DEPTH		CORE/SAMPLE		BLOWS PER FT. CORE RECVY	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
	ft.	NO.	SIZE			
0					<p>Spun 6" SW Flush coupled casing to the bottom depth of 56'.</p> <p>About 2 hrs to clear rocks so that drilling could begin.</p> <p>5 truck loads of gravel was used to make the drilling platform.</p>	<p>No samples above 29' as per instruc- tions.</p>
1						
2						
3						
4						
5						
6						
7						
8						
9						
10						

GENERAL REMARKS:

Site

Birch Hill Dam

Boring No.

PZ-14 FD-88-4

Page 3of 5

DEPTH		CORE/SAMPLE		BLOWS PER FT. CORE RECVY	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
	IN	NO.	SIZE			
10						
11						
12						
13						
14						
15						
16						
17						
18						
19						
20						
21						
22						
23						
24						
25						
26						
27						

Site					Boring No.		Page	
Birch Hill Dam					PZ-14 FD-88-4		of 8	
DEPTH		CORE/SAMPLE		BLOWS PER FT. CORE RECVY	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS		
	ft.	NO.	SIZE	DEPTH RANGE				
27								
28								
29					End Drilling 10/20/55			
30		S-1	1 3/8"	60%	12 24 40 73 Sampled with 1 3/8" I.D. spoon. Spun casing to 33'. Water based drilling fluid was used to lubricate the casing.	Dark Grey, f, SAND Little, SILT Trace, f, GRAVEL SP-SM		
31					Sampled	Grey, f, SAND Trace, SILT Trace, f, GRAVEL SP-SM		
32		S-2	1 3/8"	70%	41 13 18 9			
33					Sampled	Grey, f, SAND Trace, SILT Trace, GRAVEL SP-SM		
34		S-3	1 3/8"	60%	12 24 50 88 Sampled Spun casing to 37'.			
35					Sampled	Similar Soil Large Rock Fragments SP-SM		
36		S-4	1 3/8"	10%	18 Bouncing WATER TABLE @ 36'			
37					Sampled	Brown, mf, SAND Trace, SILT Trace, f, Gravel SP-SM		
38		S-5	1 3/8"	70%	20 28 32 34 Sampled Spun casing to 41'.			
39					Sampled	Brown, mf, SAND Some, SILT Trace - ROCK FRAGMENTS SP-SM		
40		S-6	1 3/8"	80%	34 48 49 43			
41					Sampled	Lt. Gray, SILT, some f SAND SP-SM		
42		S-7	1 3/8"	20%	23 37 47 34 Sampled Piece of coarse gravel wedged in shoe. Spun casing to 45'.			
43					Sampled	Grey, mf, SAND Trace, ROCK FRAGMENTS SP-SM		
44		S-8	2 3/8"	50%	46 45 1 3/8" spoon got blocked so the 2 3/8" spoon was used.			

DEPTH ft.	CORE/SAMPLE			BLOWS PER FT. CORE RECVY	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
	NO.	SIZE	DEPTH RANGE			
44				50		
45	S-8			45		
46	S-9	1 3/8"	80%	28 24 20 20	Sampled with 1 3/8" I.D. spoon. Spun casing to 49'.	Lt. Grey, SILT, some, F. SAND ML
47				25		
48	S-10	1 3/8"	90%	33 33 29	Sampled with 2 3/8" I.D. spoon because 1 3/8" I.D. spoon was blocked with a rock	Similar Soil ML
49				15		
50	S-11	1 3/8"	80%	16 3 21	Sampled with 1 3/8" I.D. spoon. Spun casing to 53'.	Similar Soil ML
51				45	Sampled	Similar Soil
52	S-12	1 3/8"	90%	48 50 60		ML -
53				6		
54	S-13	1 3/8"	70%	8 16 24	Sampled. Spun casing to 56'.	Similar Soil ML
55						
56					10/21/88 Set upper piezometer at 42' and lower piezometer at 55' Set steel riser pipe.	

PIEZOMETER INSTALLATION REPORT

PROJECT: Birch Hill Dam DATE: 11/19/50

LOCATION (STA): PZ-14 ^{Sta} 10+50 OFFSET FROM CENTER LINE: 35' Rt. PIEZ NO.: PZ-14

PIEZ TYPE: Casagrande DEPTH Upper 42 RISER PIPE 3/4"
OF PIEZ: Lower 55 DIAM: 3/4"

PIEZ TIP SET IN SP-SM SOIL S-7
(SOIL TYPE): ML SAMPLE NO.: S-13 BORING DIAM: 6"

METHOD OF INSTALLATION:

TYPE OF PROTECTION

FOR PIEZ: 4" Protective Pipe VENT: Screw on Cap

GROUND ELEV.: 854 ELEV. TOP Upper 857.4' ELEV 812
OF RISER: Lower 857.5' PIEZ TIP: 799

FILTER: #4 Sand FROM ELEV: Upper 807.0' TO ELEV: 819.0
Lower 798.0' 803.0

SEAL: Bentonite Pellets FROM ELEV: Upper 844 TO ELEV: 846
Lower 803 804

INSTALLED BY: Randy T. Hill CONTRACT NO.: 0008 FOREMAN: Paul Davis

DATE OF INSTALLATION: 10/21/50 DATE OF OBSERVATIONS: 11/19/50

METHOD OF

TESTING PIEZ.: Fallwater Head Test

TIME	ELAPSED TIME MINUTES	DEPTH TO WATER FEET	TIME	ELAPSED TIME MINUTES	DEPTH TO WATER FEET	TIME	ELAPSED TIME MINUTES	DEPTH TO WATER FEET
	1	0'		0	0'			
	1	30'		1	31			
	2	35		2	36			
	4	37		4	37 1/2			
	10	37		10	37 1/2			

REMARKS:

* WATER AT 39' PRIOR TO TESTING


** WATER AT 39 1/2' PRIOR TO TESTING

Christopher H. Lawrence
INSPECTOR

Site: <u>Buck Hill Dam</u> Boring No: <u>2-11</u>	SUBSURFACE WATER OBSERVATIONS
--	--------------------------------------

DATE	TIME	DEPTH-BOT. OF CASING	DEPTH-BOT. OF BORING	DEPTH TO WATER		ELEVATION WATER		REMARKS
				Upper	Lower	Upper	Lower	
10/21			5.6'	5' 1/2	11' 1/3	848.9	845.3	
11/9			5.6'	39 3/4	30 1/2	817.6	818.0	
11/11	1:30		5.6'	39 1/2	30 1/2	817.9	818.2	
11/12			5.6'	39	39	818.4	818.5	
11/15			5.6'	38	37	818.1	818.5	
11/17			5.6'	38 1/2	39	818.9	818.5	
11/18			5.6'	39	37 1/3	818.1	818.2	Falling Head Test
11/21			5.6'	39 1/3	37 1/3	818.1	818.2	
12/15	17:00			39.4	32.3	818.1	818.1	STATIC

Note: Depths are in feet below original ground



ATLANTIC TESTING LABORATORIES, LIMITED

atl

PIEZOMETER INSTALLATION DETAIL

PROJECT Birch Hill Dam, Ma.

CONTRACT No. DACW-33-87-D-0007

ATL PROJECT No. CD033

CLIENT U.S. Army Corps of Engineers
Waltham, Massachusetts

PIEZOMETER No. PZ-14

Orange Paint

TOP PROTECTIVE PIPE 857.82
TOP LOWER PIEZOMETER RISER 857.50
TOP UPPER PIEZOMETER 857.42

3/4" PVC Sch 80
Riser Pipe

Casagrande
Piezometer

Casagrande
Piezometer

	SURFACE ELEVATION	DEPTH	SOIL STRATA
Backfill	848.0'	6'	No sample as per instructions.
Bottom of Pipe	846.0'	8'	
Bentonite Seal	844.0'	10'	
Backfill		29'	Grey f SAND, trace SILT, trace GRAVEL
Water Table ∇	820.3 819.0' 818.0'	33.7 32' 36'	
Filter Sand		37'	
Tip of Piezometer	813.3 812.0'	41' 42'	Brown mf SAND, some SILT, trace ROCK FRAGMENTS, (non- plastic) SP - SM
	807.8 807.0'	46.8 47'	
Bentonite Seal	803.8 803.0'	50.2 51'	
Tip of Piezometer	799.8 799.0'	54.2 55'	Light grey SILT, some f SAND (very slightly plastic) ML
Bottom	798.0'	56'	

per USACE Measurements
1 Feb 89
ATL

CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site Bisc. Hill Dr. PROJECT NO. CD-033
Page 1 of 8 Pages
Hole No. PZ-12 Diam. (Casing) 6" SW Boring Started 11/3/82
FD-88-S
Co-ordinates: N 594926 E 432087 Boring Completed 11/9/82
Drilled by T. J. Price Report Submitted 12/21/82

Purpose of Exploration: Install 2 piezometers

Elevation Top of Hole 297.9467 M.S.L. Casing Left in Place 4" DIA. - 10 Feet
Total Overburden Drilled 51' Feet
Elevation Top of Rock _____ M.S.L.
Elevation Bottom of Hole 297.7957 M.S.L.
Total Rock Drilled _____ Feet
Total Depth of Hole 51' Feet
Core Recovered _____ %
Core Recovered _____ Ft.; _____ Dia. _____ In.
Soil Samples 1 $\frac{3}{8}$ " ID In. Dia. 11 No.
Soil Samples _____ In. Dia. _____ No. Water Table Depth 31

Depth		Method of Drilling and Type of Bit Used
From	To	
0	30'	Rounded 6" SW Flush coupled casing
0	25'	No samples as per instructions
25	50	Continuous sampling
48	50	Lower piezometer (grey)
40	42	Upper piezometer (orange)
0	3'	4x5 1/2" Core

INDEX	
Ground Water	Back of Page <u>7</u>
Boring Location Sketch	Back of Page <u>7</u>
Overburden Record	pages <u>2-5</u> Page _____
Rock Drilling	Page _____
Piezometer Installation Report	Page <u>6</u>
" " " " " "	DETAIL Page <u>8</u>
" " " " " "	Page _____

Prepared by Christopher H. Lawrence
Field Data

Submitted by ATLANTIC TESTING LABORATORIES
Lab. Data

U. S. ARMY
CORPS OF ENGINEERS
NEW ENGLAND DIVISION

Site Birch Hill Dam Page 2 of 8 Pages
Boring No. P2-12 Desig. _____ Diam. (Casing) 6"
FD-88-5
Co-ordinates: N 594926 E 432037

FIELD LOG OF TEST BORING

Elevation Top of Boring 848 M.S.L. Hammer Wt. 140 lbs Boring Started 11/3/52
Total Overburden Drilled 51 Feet Hammer Drop 30"
Elevation Top of Rock _____ M.S.L. Casing Left 10' Boring Completed 11/8/52
Total Rock Drilled _____ Feet Subsurface Water Data _____ Page 7
Elevation Bottom of Boring 797 M.S.L. Obs. Well _____
Total Depth of Boring 51 Feet Drilled By T. J. + Price
Core Recovered _____ % No. Boxes _____ Mfg. Des. Drill _____
Core Recovered _____ Ft : _____ Diam. _____ In. Inspected By: Christopher H. Lawrence
Soil Samples 1 3/8" In. Diam. 11 No. Classification By: Christopher H. Lawrence
Soil Samples _____ In. Diam. _____ No. Classification By: _____

DEPTH	CORE/SAMPLE			BLOWS PER FT. CORE REC'Y	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
	NO.	SIZE	DEPTH RANGE			
0					<p>Drilled with 5 7/8" roller bit and water. Then pounded the 6" casing to 25' with 300 lbs hammer.</p> <p>Took about 2 hours to get through the surface rocks, with 4 x 5 1/2' Core from 0-3'.</p>	No samples above 28' as per instructions.
1						
2						
3						
4						
5						
6						
7						
8						
9						
10						

GENERAL REMARKS:

Site <i>Birch Hill Dam</i>					Boring No. <i>P2-12 FD-88-5</i>		Page <i>2</i> of <i>8</i>	
DEPTH		CORE/SAMPLE			BLOWS PER FT. CORE RECVY	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS	
	IN	NO.	SIZE	DEPTH RANGE				
10								
11								
12								
13								
14								
15								
16								
17								
18								
19								
20								
21								
22								
23								
24								
25						<i>End Drilling 11/3/88</i>		
26								
27								

Site				Boring No.		Page <u>4</u>
Birch Hill Dam				PZ-12 FD-88-5		of <u>8</u>
DEPTH	CORE/SAMPLE		BLOWS PER FT.	SAMPLING AND CORING OPERATIONS		CLASSIFICATION OF MATERIALS
	NO.	SIZE	DEPTH RANGE	CORE RECVY		
27						
28				15	Sampled with 1 3/8" I.D. spoon advanced with 140 lbs hammer Drilled to 30' and advanced casing to 30'.	Yellow Brown, cmf, SA. Little, mf, GRAVEL Trace, SILT SP-SM
29	S-1	1 3/8"	80%	26		
				37		
30				51	End Drilling 11/4/88 (continued)	
				38	Sampled	Brown, mf, SAND Trace, SILT Trace, F, GRAVEL SP-SM
31	S-2	1 3/8"	90%	73		
				88		
32				82	End Drilling 11/7/88	
				50	Sampled	Similar Soil
33	S-3	1 3/8"	85%	56		
				62		
34				74		
				11	Sampled Drilled to 38' with 5 7/8" roller bit and water based drilling fluid to hold the hole open.	Similar Soil
35	S-4	1 3/8"	27%	26		
				41		
36				47		
				46	Sampled	Similar Soil Little, mf, GRAVEL
37	S-5	1 3/8"	50%	68		
				98		
38				100		
				31	Sampled Drilled to 42' with 5 7/8" roller bit and water based drilling fluid.	Yellow Brown, cmf, SAND Little, mf, GRAVEL; Trace, SILT SP-SM
39	S-6	1 3/8"	90%	21		
				25		
40				39		
				28	Sampled	Similar Soils
41	S-7	1 3/8"	70%	26		
				27		
42				25		
				16	Sampled Drilled to 46' with 5 7/8" roller bit and water based drilling fluid.	Lt Grey, SILT, some F, SAND Little, CLAY ML (USP)
43	S-8	1 3/8"	70%	13		
				14		
44				22		

Site					Boring No.		Page <u>5</u>
Birch Hill Dam					PZ-12 FD-88-5		of <u>8</u>
DEPTH		CORE/SAMPLE		BLOWS PER FT.	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS	
	ft.	NO.	SIZE	DEPTH RANGE			CORE RECVY
44					8 Sampled	Similar Soil	
45		S-9	1 3/8"	90%	11 14 16		
46					12		
47		S-10	1 3/8"	90%	11 15 13 Sampled Drilled to 51' with 5 7/8" roller bit and water based drilling fluid.	Similar Soil	
48					8		
49		S-11	1 3/8"	90%	7 8 9 Sampled	Similar Soil	
50							
51					Drilled to 51' with 5 7/8" roller bit and water based drilling fluid. Drove SW to 30'. 11/8/88 - Completed drilling, sampling, and set upper piezometer at 42' (orange) and lower piezometer at 50' (gray). Hole was drilled an extra 3 feet on Terry Wong's recommendation to make enough room for both piez- ometers in their proper sand/gravel layers		

PIEZOMETER INSTALLATION REPORT

PROJECT: Birch Hill Dam DATE: 11/9/11

LOCATION (STA): PZ 12 Sta 7+00 OFFSET FROM CENTER LINE: 60' Left PIEZ NO.: PZ-12

PIEZ TYPE: Casagrande DEPTH Upper 40-42 RISER PIPE 3/4"

PIEZ TIP SET IN SP-SM OF PIEZ: Lower 48-50 DIAM: 6"

(SOIL TYPE): ML SOIL S-7 SAMPLE NO.: S-11 BORING DIAM: 6"

METHOD OF INSTALLATION:

TYPE OF PROTECTION FOR PIEZ:

4" Protective Pipe

VENT: Screw on Cap

GROUND ELEV.: 848 846.7 ELEV. TOP Upper 849.89 ELEV 804.7

OF RISER: Lower 849.35 PIEZ TIP: 796.7

FILTER: #4 Sand FROM ELEV: Upper 803.7 TO ELEV: 811.7

Lower 795.7 TO ELEV: 799.7

SEAL: Bentonite Pellets FROM ELEV: Upper 836.7 TO ELEV: 840.7

Lower 799.7 TO ELEV: 803.7

INSTALLED BY: E. L. T. CONTRACT NO.: 0008 FOREMAN:

DATE OF INSTALLATION: 11/2/11 DATE OF OBSERVATIONS: 11/9/11

METHOD OF TESTING PIEZ.: Falling Head Test

TIME	ELAPSED TIME MINUTES	DEPTH TO WATER FEET	TIME	ELAPSED TIME MINUTES	DEPTH TO WATER FEET	TIME	ELAPSED TIME MINUTES	DEPTH TO WATER FEET
		* 0'		0	** 0			
	1	20'		1	22'			
	3	31'		3	24'			
	5	31 1/2'		5	22'			
	10	31 1/2'		10	22'			

REMARKS:

* Water at 29 3/4' prior to test.

** Water at 28' prior to test.


Christopher H. Lawrence
INSPECTOR

Site: Brown Lake Dam
 Boring No: PZ-12

SUBSURFACE WATER OBSERVATIONS

DATE	TIME	DEPTH-BOT. OF CASING	DEPTH-BOT. OF BORING	DEPTH TO WATER		ELEVATION WATER		REMARKS
				upper	lower	upper	lower	
11/10	1:20		51	29	28	819	820	
11/19			51	29 3/4	28	818 1/4	820	Falling Head Tests
11/1			51	31 1/2	32	816 1/2	816	
11/10			-	30	30	818	818	GROUND ELEV. WAS 846 NO. 848
11/10			-	28	27	820	819	ALL ELEV. SHOULD BE 1.3 FT LOWER
11/10			51	29	30	819	818	
11/17			51	27	30	819	818	
11/20			51	31	32	817	816	
12/5	1 PM			33.8	*	816.1		STATIC
* Could not obtain reading due to obstruction at 6' - later determined riser was broken; new installation has been made.								

Note: Depths are in feet below original ground



ATLANTIC TESTING LABORATORIES, LIMITED

atl

PIEZOMETER INSTALLATION DETAIL


PROJECT Birch Hill Dam, Ma.

CONTRACT No. DACW-33-87-D-0007

CLIENT U.S. Army Corps of Engineers
Waltham, Massachusetts

ATL PROJECT No. CD033

PIEZOMETER No. PZ-12



ATLANTIC TESTING LABORATORIES, LIMITED

atl

PIEZOMETER INSTALLATION DETAIL

PROJECT Birch Hill Dam, MA

CONTRACT No. DACW-33-87-D-0007


CLIENT U.S. Army Corps of Engineers
Waltham, MA

ATL PROJECT No. CD033

PIEZOMETER No. PZ-12A

Piezometer was installed adjacent to the original piezometer location (PZ-12).
Installed 2/1 and 2/2/89.

TOP PROTECTIVE PIPE _____
TOP LOWER PIEZOMETER RISER _____
TOP UPPER PIEZOMETER _____



CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site Birds Hill Dam PROJECT NO. CD-033
 Hole No. PF-13 Diam. (Casing) 6" SGI Page 1 of 7 Pages
FD-88-6
 Co-ordinates: N 594935 E 432018 Boring Started 11/10/88
 Drilled by Ted + Pryce Boring Completed 11/11/88
 Report Submitted 12/21/88

Purpose of Exploration Install 2 piezometers

Elevation Top of Hole 832 M.S.L. Casing Left in Place 4" DIA. - 10 Feet
 Total Overburden Drilled 34 Feet
 Elevation Top of Rock _____ M.S.L.
 Elevation Bottom of Hole 798 M.S.L.
 Total Rock Drilled _____ Feet
 Total Depth of Hole 34 Feet
 Core Recovered _____ %
 Core Recovered _____ Ft.; _____ Dia. _____ In.
 Soil Samples 1 3/8" In. Dia. 11 No.
 Soil Samples _____ In. Dia. _____ No.
 Water Table Depth 18'

Depth		Method of Drilling and Type of Bit Used
From	To	
0	20	Spun 6" Flush coupled casing
0	10	No samples as per instructions
10	22	Continuous sampling
23	25	Upper piezometer (orange)
31	33	Lower piezometer (gray)

INDEX	
Ground Water _____	Back of Page <u>6</u>
Boring Location Sketch _____	Back of Page <u>6</u>
Overburden Record <u>pages 2-4</u>	Page _____
Rock Drilling _____	Page _____
<u>Piezometer Installation Report</u>	Page <u>5</u>
" " <u>DETAIL</u>	Page <u>7</u>
" " _____	Page _____

Prepared by Christopher H. Lawrence
 Field Data

Submitted by ATLANTIC TESTING LABORATORIES

Lab. Data _____

U. S. ARMY
CORPS OF ENGINEERS
NEW ENGLAND DIVISION

Site Birch Hill Dam Page 2 of 7 Pages

Boring No. P2-13 Desig. _____ Diam. (Casing) 6"
FD-88-6

FIELD LOG OF TEST BORING

Co-ordinates: N 594935 E 432018

Elevation Top of Boring 532 M.S.L. Hammer Wt. 145 lbs Boring Started 11/10/55
Total Overburden Drilled 34 Feet Hammer Drop 30"
Elevation Top of Rock _____ M.S.L. Casing Left 10' Boring Completed 11/11/55
Total Rock Drilled _____ Feet | Subsurface Water Data _____ Page 6
Elevation Bottom of Boring 798 M.S.L. | Obs. Well _____
Total Depth of Boring 34 Feet | Drilled By Todd + Pryce
Core Recovered _____ % No. Boxes _____ Mfg. Des. Drill _____
Core Recovered _____ Ft : _____ Diam. _____ In. | Inspected By: Christopher H. Lawrence
Soil Samples 1 3/8 In. Diam. 11 No. | Classification By: Christopher H. Lawrence
Soil Samples _____ In. Diam. _____ No. | Classification By: _____

DEPTH		CORE/SAMPLE			BLOWS PER FT. CORE REC'Y	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
	I" -	NO.	SIZE	DEPTH RANGE			
0						Advance 6" SW Flushing coupled casing to 20'	No samples above, 10' as per instruction
1							
2							
3							
4							
5							
6							
7							
8							
9							
10							
GENERAL REMARKS:							

Site					Boring No.		Page <u>3</u>
Birney Hill Dam					PZ-13 FD-88-6		of <u>7</u>
DEPTH		CORE/SAMPLE		BLOWS PER FT. CORE RECVY	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS	
	ft.	NO.	SIZE				
10				31	Sampled with 1 3/8" I.D.	Lt. Brown, mf, SAND Trace, SILT Trace, GRAVEL SP-SM (NP)	
11		S-1	1 3/8"	30	Special advanced with 140 lbs		
				21	hammer.		
12				29	Drilled to 14' with 5 7/8" roller	Similar Soil Little, mf, GRAVEL + Rock fr.	
				29	bit and water based drilling		
				29	fluid.		
13		S-2	1 3/8"	33	Sampled	SP-SM (NP)	
				21			
				26			
14				36	Sampled	Similar Soil (NP) SP-SM	
15		S-3	1 3/8"	22	Drilled to 18' with 5 7/8" roller		
				30	bit and water based drilling		
16				36	fluid.	Similar Soil (NP) SP-SM	
				29	Sampled		
17		S-4	1 3/8"	27	OBSTRUCTION AT 18'		
				45	LOST DOWN WATER.	No Sample because of obstruction @ 18'	
18				28	STOP CASING TO 20'		
					Water Table		
19		S-5	1 3/8"		Sampled	Lt. Brn, cmf, SAND Trace, SILT Little, f, GRAVEL (NP) SP-SM	
					Drilled to 22' with 5 7/8"		
					roller bit and water based		
20					drilling fluid.		
					- Reamed - 6" casing		
					WATER RECOVERY O.K.		
21		S-6	1 3/8"	24		Lt. Brown, Grey, cmf SAND; Trace, SILT Little, mf, GRAVEL + (NP) SP-SM ROCK FRAG.	
				30			
				51			
22				62	Sampled	③ Grey, cmf, SAND Trace, SILT Trace, f, GRAVEL ④ Lt. Grey, -SILT, some f, SAND Little, clay (NP) CL-ML	
23		S-7	1 3/8"	41	Drilled to 26' with 5 7/8"		
				39	roller bit and water based		
24				37	drilling fluid	Lt. Grey, SILT, some f SAND Trace, f, GRAVEL	
				25	Sampled		
				13			
25		S-8	1 3/8"	13			
				14			
				14			
26					Sampled		
					Drilled to 30' with 5 7/8"		
27		S-9	1 3/8"	7	roller bit and water based		
				11	drilling fluid		

Site					Boring No.		Page	
Birch Hill Dam					72-12 FD-88-6		of 7	
DEPTH		CORE/SAMPLE			BLOWS PER FT. CORE RECVY	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS	
FEET	INCHES	NO.	SIZE	DEPTH RANGE				
27		S-9	1 3/8"	100%	9	Sampled	Trace, CLAY (USP)	
28					11		ML-CL	
29		S-10	1 3/8"	100%	6		Lt. Grey, SILT, some F, SAND	
30					6		Some, CLAY (USP)	
31		S-11	1 3/8"	95%	6	Sampled Drilled to 34' with 5 7/8" roller bit and water based drilling fluid.	ML-CL	
32					6		Similar Soil (USP)	
33								
34								
						Bottom of hole		
						11/10/55 - Complete drilling, sampling.		
						11/11/55 - Set upper piezometer at 25' (orange), lower piezometer 33' (grey)		

PIEZOMETER INSTALLATION REPORT

PROJECT: Port of Los Angeles DATE: 11/21/88
 LOCATION (STA): P2-13 Sta 7+00 OFFSET FROM CENTER LINE: 130' Left PIEZ NO.: 72-13
 PIEZ TYPE: Casagrande DEPTH Upper 23 25 RISER PIPE 3/4"
 OF PIEZ: Lower 31-33 DIAM: 3/4"
 PIEZ TIP SET IN SP-SM SOIL S-7
 (SOIL TYPE): CL-ML SAMPLE NO.: S-11 BORING DIAM: 6"

METHOD OF INSTALLATION:

TYPE OF PROTECTION

FOR PIEZ:

4" diameter Protective Pipe VENT: Screw on Cap

GROUND ELEV.: 832.5

ELEV. TOP Upper 834.64 ELEV 807.5
 OF RISER: Lower 834.62 PIEZ TIP: 799.5

FILTER: #4 Sand

FROM ELEV: Upper 806.5 TO ELEV: 814.5
 Lower 798.5 802.5

SEAL: Bentonite Pellets

FROM ELEV: Upper 822.5 TO ELEV: 826.5
 Lower 802.5 806.5

INSTALLED BY: Crane & Tool

CONTRACT

NO.: 0008

FOREMAN:

DATE OF INSTALLATION: 11/11/88DATE OF OBSERVATIONS: 11/21/88

METHOD OF

TESTING PIEZ.: Falling Head Test

TIME	ELAPSED TIME MINUTES	DEPTH TO WATER FEET	TIME	ELAPSED TIME MINUTES	DEPTH TO WATER FEET	TIME	ELAPSED TIME MINUTES	DEPTH TO WATER FEET
	0	0'*		0	0'*			
	1/2	15'		1/2	15'			
	1	15'		1	17 1/2'			
	5	15'		5	17 1/2'			
	10	15'		10	17 1/2'			

REMARKS:

* Water at 18' prior to test.


* * Water at 17 1/2' prior to test.

Christopher H. Lawrence
 INSPECTOR

Site: <u>Brown Line Down</u>	SUBSURFACE WATER OBSERVATIONS
Boring No: <u>DZ-17</u>	

DATE	TIME	DEPTH-BOT. OF CASING	DEPTH-BOT. OF BORING	DEPTH TO WATER		ELEVATION WATER		REMARKS
				Upper	Lower	Upper	Lower	
11/14			34'	18 1/2	18 3/4	813 1/2	813 1/4	
11/15			34'	18	18 1/2	814	813 1/2	
11/17			34'	12 1/4	12 1/4	812 3/4	812 3/4	
11/19			34'	18	18	814	814	
11/21			34'	17 1/2	18	814 1/4	814	Falling Water Table
12/15	1 PM			19.0	19.1	815.6	815.5	STATIC

Note: Depths are in feet below original ground



ATLANTIC TESTING LABORATORIES, LIMITED

atl

PIEZOMETER INSTALLATION DETAIL

PROJECT Birch Hill Dam, Ma.

CONTRACT No. DACW-33-87-D-0007

CLIENT U.S. Army Corps of Engineers
Waltham, Massachusetts

ATL PROJECT No. CD033

PIEZOMETER No. PZ-13

Orange Paint

TOP PROTECTIVE PIPE 835.22
TOP LOWER PIEZOMETER RISER 834.62
TOP UPPER PIEZOMETER 834.64

4" PVC Sch 80
Riser Pipe

Large
Piezometer

Large
Piezometer

SURFACE
ELEVATION

832.5'

DEPTH

SOIL STRATA

Backfill

826.5'

6'

No samples as per instructions.

Bottom of Pipe

824.5'

8'

Bentonite Seal

822.5'

10'

Backfill
(Sand)

Light brown mf SAND, trace SILT, trace GRAVEL and ROCK FRAGMENTS (non-plastic) SP-SM

Water Table

814.5'

18'

No sample because of an obstruction.

Filter Sand

20'

Light brown cmf SAND, little f GRAVEL, trace SILT (non-plastic) SP - SM

Tip of Piezometer

808.8

23.7

807.5'

25'

806.5'

26'

808.0

24.5'

28'

Light grey SILT, some f SAND, little CLAY (very slightly plastic) ML - CL

804.0

28.5'

802.5'

30'

Light grey SILT, some f SAND, some CLAY (very slightly plastic) ML - CL

Filter Sand

801.0

31.5'

799.5'

33'

Tip of Piezometer

798.5'

34'

Bottom

P. - USACE measurement on 1 Feb 88

Site Birch Hill Dam PROJECT NO. CD-033
 Hole No. PP-16 Diam. (Casing) 6" SW Page 1 of 8 Pages
FD-88-7
 Co-ordinates: N 594577 E 432055 Boring Started 11/16/88
 Drilled by Ts. J. + Pryor Boring Completed 11/17/88
 Report Submitted 12/21/88

Purpose of Exploration Instali 2 piezometry.

Casing Left In Place 4" D.A. - 10 Feet

Water Table Depth $\approx 30'$

Depth		Method of Drilling and Type of Bit Used
From	To	
0	15	Spun 6" SW Flush coupled casing
15	49	Drilled open hole with 5 1/2" roller bit
0	26	No samples as per instructions
26	45	Continuous samples
46	42	Lower Piezometer (prev.)
24	36	Upper Piezometer (orange)

INDEX	
Ground Water _____	Back of Page 7
Boring Location Sketch _____	Back of Page 7
Overburden Record <u>pages 2-5</u>	Page _____
Rock Drilling _____	Page _____
<u>Piezometer Installation</u>	<u>REPORT</u> Page 6
" "	<u>DETAILS</u> Page 7
	Page _____

Prepared by Christopher H. Lawrence

Submitted by ATLANTIC TESTING LABORATORIES

DEPTH	Ft.	CORE/SAMPLE NO.	SIZE	DEPTH RANGE	BLOWS PER FT. CORE RECVY	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
10							
11							
12							
13							
14							
15						Bottom of 6" casing. Below 15' the drilling was open hole with a 5 7/8" roller bit and water based drilling fluid to keep the hole open.	
16							
17							
18							
19						— Water Table	
20							
21							
22							
23							
24							
25							
26							
27		5-1	1 3/8"	80%	59 71	Sampled with 1 3/8" I.D. spoon advanced with 140 lbs hammer.	Brown, mF, SAND Trace, m, ROCK FRAGMENTS Trace SILT SP-SM

Birch Hill Dam

PZ-16 FD-88-7

of 3

DEPTH	CORE/SAMPLE			BLOWS PER FT. CORE RECVY	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
	NO.	SIZE	DEPTH RANGE			
27	S-1	1 3/8"	80%	39 54	Sampled	(A) Lt. Brown, f, SAND Trace, SILT (B) Yellow Brown, mf, SP-SM Trace, SILT Trace, mf, GRAVEL (np) SP-SM
28				71		
29	S-2	1 3/8"	70%	74 105		
30					5" penetration - no problem drilling through	
31	S-3	1 3/8"	80%	41 56 67 100	Sampled Drilled and washed to a depth of 34' with 5 7/8" roller bit and water based drilling fluid. End Drilling 11/16/88	Similar Soil to (B) SP-SM
32					Sampled	No sample because of obstruction
33	S-4	1 3/8"	10%	100	4" penetration - Drilled through in about 10 min.	
34					3" penetration - Drilled through in about 15 min.	
35	S-5	1 3/8"	70%	20 31 29 40	Sampled Drilled and washed to 38' with 5 7/8" roller bit and water based drilling fluid.	Dk Brown, mf, SAND Trace, SILT (np) SP-SM
36					Sampled	Lt. Brown, mf, SAND Trace, SILT (np) SP-SM
37	S-6	1 3/8"	80%	25 24 36 32		
38					Sampled	
39	S-7	1 3/8"	70%	10 8 8 14	Drilled and washed to 42' with 5 7/8" roller bit and water based drilling fluid.	Lt. Grey, SILT, mf f, SAND (usp) ML
40					Sampled	Same Soil (usp) ML
41	S-8	1 3/8"	70%	9 12 13 14		
42					Sampled	
43	S-9	1 3/8"	80%	8 12 16 14	Drilled and washed to 46' with 5 7/8" roller bit and water based drilling fluid.	Same Soil (usp) ML
44						

DEPTH	CORE/SAMPLE			BLOWS PER FT. CORE REC'D	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
	NO.	SIZE	DEPTH RANGE			
44				14	Sampled	Same Soil (U= P) ML
45	S-10	1 3/8"	80%	11 15		
46				15		
47	S-11	1 3/8"	85%	7 8 17 32	Sampled Drilled and washed to 49' with 5 7/8" roller bit and water based drilling fluid.	Same Soil (U= P) ML
48						
49					Bottom of hole. 11/17/88 - Finished drilling and set piezometers. Upper piezometer at 36' (orange) Lower piezometer 42' (grey) 11/18/88 Finished piezometers and set tentative pipe	

PIEZOMETER INSTALLATION REPORT

PROJECT: Birch Hill Dam

DATE: 11/19/82

LOCATION (STA): PZ-16 Sta 10+50 OFFSET FROM CENTER LINE: 60' Left PIEZ NO.: PZ-16

PIEZ TYPE: Casagrande DEPTH Upper 34-36 RISER PIPE 3/4"

PIEZ TIP SET IN Upper SP-SM OF PIEZ: Lower 46-48 DIAM: 3/4"

(SOIL TYPE): Lower ML SOIL S-5 SAMPLE NO.: S-11 BORING DIAM: 6"

METHOD OF INSTALLATION:

TYPE OF PROTECTION FOR PIEZ: 4" diameter Protective Pipe VENT: Screw on Cap

GROUND ELEV.: 848.4 ELEV. TOP Upper 850.88 ELEV 800.4 OF RISER: Lower 850.97 PIEZ TIP: 812.4

FILTER: #4 Sand FROM ELEV: Upper 810.4 TO ELEV: 818.4 Lower 799.4 TO ELEV: 806.4

SEAL: Bentonite Pellets FROM ELEV: Upper 840.4 TO ELEV: 842.4 Lower 806.4 TO ELEV: 810.4

INSTALLED BY: Cindy Tordella CONTRACT NO.: 0008 FOREMAN:

DATE OF INSTALLATION: 11/18/82 DATE OF OBSERVATIONS: 11/19/82

METHOD OF TESTING PIEZ.: Falling Head Test

TIME	ELAPSED TIME MINUTES	DEPTH TO WATER FEET	TIME	ELAPSED TIME MINUTES	DEPTH TO WATER FEET	TIME	ELAPSED TIME MINUTES	DEPTH TO WATER FEET
	0	0' 4"		0	0' 4"			
	1/2	30		1/2	32			
	1	31 1/2		1	26			
	3 3/4	31 1/2		2	25 1/2			
	5	31 1/2		5	26 1/2			

REMARKS:

* Water at 31 1/2' prior to test.

* Water at 26 1/2' prior to test.

Christopher H. Lawrence
INSPECTOR


Site: Brown L. Drain

Boring No: 20-12

SUBSURFACE WATER OBSERVATIONS

DATE	TIME	DEPTH-BOT. OF CASING	DEPTH-BOT. OF BORING	DEPTH TO WATER		ELEVATION WATER		REMARKS
				Upper	Lower	Upper	Lower	
11/10				20	25	830	825	
11/11				26	31	824	819	
11/12				26 1/2	31 1/2	823 1/2	819 1/2	Falling Head Test
11/13				27	32	823	818	
12/15	1 PM			33.1	32.4	817.8	818.6	STATIC

Note: Depths are in feet below original ground



ATLANTIC TESTING LABORATORIES, LIMITED

atl

PIEZOMETER INSTALLATION DETAIL

PROJECT Birch Hill Dam, Ma.

CONTRACT No. DACW-33-87-D-0007

CLIENT U.S. Army Corps of Engineers
Waltham, Massachusetts

ATL PROJECT No. CD033

PIEZOMETER No. PZ-16


Orange Paint

TOP PROTECTIVE PIPE 851.67
TOP LOWER PIEZOMETER RISER 850.97
TOP UPPER PIEZOMETER 850.88

4" PVC Sch 80
Riser Pipe

Asagrande
Piezometer

Asagrande
Piezometer



CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site Birch Hill Dam PROJECT NO. CD-033
Page 1 of 7 Pages

Hole No. PZ-17 Diam. (Casing) 6" SW
FD-88-8

Co-ordinates: N 594578 E 431981

Drilled by Todd + Pryce

Boring Started 11/19/88

Boring Completed 11/21/88

Report Submitted 12/21/88

Purpose of Exploration Install 2 piezometers.

Elevation Top of Hole 832 H.S.L.

Casing Left in Place 4" DIA. 10 Feet

Total Overburden Drilled 34 Feet

Elevation Top of Rock _____ H.S.L.

Elevation Bottom of Hole _____ H.S.L.

Total Rock Drilled _____ Feet

Total Depth of Hole 34 Feet

Core Recovered _____ %

Core Recovered _____ Ft.; _____ Dia. _____ In.

Soil Samples 1 3/4 I.D. In. Dia. 11 No.

Soil Samples _____ In. Dia. _____ No.

Water Table Depth ≈ 17'

Depth		Method of Drilling and Type of Bit Used
From	To	
0	15	Spun 6" SW Flush Coupled Casing
10	34	Drilled Open hole with roller bit
0	10	No samples as per instructions
10	32	Continuous Samples
33	31	Lower Piezometer (grey)
24	22	Upper Piezometer (orange)

INDEX	
Ground Water _____	Back of Page <u>6</u>
Boring Location Sketch _____	Back of Page <u>6</u>
Overburden Record <u>pages 2-4</u>	Page _____
Rock Drilling _____	Page _____
<u>Piezometer Installation REPORT</u>	Page <u>5</u>
<u>DETAIL</u>	Page <u>7</u>
	Page _____

Prepared by Christopher H. Lawrence Field Data
Submitted by ATLANTIC TESTING LABORATORIES Lab. Data

U. S. ARMY
CORPS OF ENGINEERS
NEW ENGLAND DIVISION

Site Birch Hill Dam Page 2 of 7 Pages

Boring No. PE-17 Desig. _____ Diam. (Casing) 6"

FD 88-8

FIELD LOG OF TEST BORING

Co-ordinates: N 594578 E 431981

Elevation Top of Boring 832 M.S.L. Hammer Wt. 140 Boring Started 11/17/82
Total Overburden Drilled 34 Feet Hammer Drop 30" Boring Completed 11/21/82
Elevation Top of Rock _____ M.S.L. Casing Left _____
Total Rock Drilled _____ Feet Subsurface Water Data _____ Page 6
Elevation Bottom of Boring 798 M.S.L. Obs. Well _____
Total Depth of Boring 34 Feet Drilled By Tedd + Pryce
Core Recovered _____ % No. Boxes _____ Mfg. Des. Drill _____
Core Recovered _____ Ft : _____ Diam. _____ In. Inspected By: Christopher H. Lawrence
Soil Samples 1 3/4" I.D. In. Diam. 11 No. Classification By: Christopher H. Lawrence
Soil Samples _____ In. Diam. _____ No. Classification By: _____

DEPTH	CORE/SAMPLE			BLOWS PER FT. CORE RECVY	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
	NO.	SIZE	DEPTH RANGE			
0					Advanced 6" SW flush coupled casing to 10'. The hole was moved about 5' south because of large boulders with Tony Firicano's permis- sion. The hole is at the same elevation.	No samples above 10' as per instruc- tions.
1						
2						
3						
4						
5						
6						
7						
8						
9						
10						

GENERAL REMARKS:

Site					Boring No.		Page <u>3</u>
Birch Hill, D. Conn.					PZ-17 FD-88-8		of <u>7</u>
DEPTH		CORE/SAMPLE		BLOWS PER FT. CORE RECVY	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS	
	ft.	NO.	SIZE	DEPTH RANGE			
10		S-1	1 3/8"	20%	16	Sampled Drilled open hole with 5 7/8" roller bit and washed to 14'. Hole was kept open with a drilling fluid.	Lt. Brown + Gray, mf, SAND Trace, SILT Little, mf, GRAVEL (np) SP-SM
11					12		
12					52		
13					36		
13		S-2	1 3/8"	70%	53	Sampled Drilled open hole and wash- ed to 14'.	Similar Soil Trace, ROCK FRAG. (np) SP-SM
14					58		
15					58		
15		S-3	1 3/8"	0%	20	Obstruction - 0" penetration with spm. Drilled about 1 1/2 hours before breaking through the rock at 17'	No Sample because of obstruction.
16					0		
16		S-4	1 3/8"	0%	5	6" casing was advanced to a depth of 15' by spinning. Rest of hole was drilled as open hole.	No Sample because of obstruction.
17					17		
18					22		
19					22		
20		S-5	1 3/8"	60%	19	Sampled Drilled + washed to 22'	Dark Red Brown, mf, SAND Trace, SILT (np) SP-SM
21					9		
22					14		
23					14		
23		S-6	1 3/8"	70%	13	Sampled	Similar Soil (np) SP-SM
24					8		
25					16		
26					13		
26		S-7	1 3/8"	70%	12	Sampled Drilled and washed to 26'	Lt. Brown, mf, SAND Trace, SILT Trace, ROCK FRAGMENT (np) SP-SM
27					6		
28					8		
29					13		
29		S-8	1 3/8"	20%	25	Sampled	Gray + Brown, mf, SAND Trace, SILT Trace, GRAVEL (np) SP-SM
30					3		
31					4		
32					30'		
32		S-9	1 3/8"	8%	3	Sampled Drilled and washed to 30'	Lt. Gray, SILT, some, F, SAND ML
33					4		

Site					Boring No.		Page	
Birch Hill (Down)					P2-17 FD-88-8		7 of 7	
DEPTH		CORE/SAMPLE		BLOWS PER FT. CORE RECY	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS		
IN	NO.	SIZE	DEPTH RANGE					
27		S-9	1 3/8"	20'	3	(USP)		
28					6			
29		S-10	1 3/8"	20'	3	Sampled		
30					2	Similar Soil		
31		S-11	1 3/8"	20'	4	(USP) ML		
32					5			
33					6	Sampled		
34					9	Drilled and washed to 34'		
35					15	11/19/82 End Drilling & Sampling		
36						Washed hole to 34'		
37						with 5 7/8" roller bit,		
38								
39								
40								
41								
42								
43								
44								
45								
46								
47								
48								
49								
50								
51								
52								
53								
54								
55								
56								
57								
58								
59								
60								
61								
62								
63								
64								
65								
66								
67								
68								
69								
70								
71								
72								
73								
74								
75								
76								
77								
78								
79								
80								
81								
82								
83								
84								
85								
86								
87								
88								
89								
90								
91								
92								
93								
94								
95								
96								
97								
98								
99								
100								

PIEZOMETER INSTALLATION REPORT

PROJECT: B-1. H.A. Dams DATE: 11/21/00

LOCATION (STA): PZ-17 Sta 10+50 OFFSET FROM CENTER LINE: 130' Left PIEZ NO.: PZ-11

PIEZ TYPE: Casa Grande DEPTH Upper 22-24 RISER PIPE 3/4"

PIEZ TIP SET IN Upper SP-SM SOIL S-7

(SOIL TYPE): Lower ML SAMPLE NO.: S-11 BORING DIAM: 6"

METHOD OF INSTALLATION:

TYPE OF PROTECTION
FOR PIEZ:

4" diameter Protective Pipe VENT: Screw on Cap

GROUND ELEV.: 831.8 ELEV. TOP Upper 834.39 ELEV 807.8

OF RISER: Lower 834.38 PIEZ TIP: 798.8

FILTER: #4 Sand FROM ELEV: Upper 805.8 TO ELEV: 814.8

SEAL: Rentonite Pellets FROM ELEV: Upper 823.8 TO ELEV: 827.8

INSTALLED BY: Randy Todd CONTRACT NO.: 0008 FOREMAN:

DATE OF INSTALLATION: 11/19/00

DATE OF OBSERVATIONS: 11/21/00

METHOD OF
TESTING PIEZ.: Falling Head Test

TIME	ELAPSED TIME -MINUTES	DEPTH TO WATER FEET	TIME	ELAPSED TIME -MINUTES	DEPTH TO WATER FEET	TIME	ELAPSED TIME -MINUTES	DEPTH TO WATER FEET
	0	0' 1/2"		0	0' 1/2"			
	1/2	12'		1/2	15'			
	1	15 1/2'		1	15 1/2'			
	5	15 1/2'		5	15 1/2'			
	10	15 1/2'		10	15 1/2'			

REMARKS:

* Water level at 18 1/2' prior to test.


* Water level at 18 1/2' prior to test.

Christopher H. Lawrence
INSPECTOR

ATLANTIC TESTING LABORATORIES, LIMITED

atl

PIEZOMETER INSTALLATION DETAIL

PROJECT Birch Hill Dam, Ma.CONTRACT No. DACW-33-87-D-0007ATL PROJECT No. CD033CLIENT U.S. Army Corps of Engineers
Waltham, MassachusettsPIEZOMETER No. PZ-17range
aintTOP PROTECTIVE PIPE 834.70TOP LOWER PIEZOMETER RISER 834.38TOP UPPER PIEZOMETER 834.491/4" PVC Sch 80
riser Pipeasagrande
piezometerasagrande
piezometer

Birch Hill Dam Drawings

General Plan

Piezometer Location Plan

Cross-Section (3)

Piezometer Installation Detail (2)

ELEVATION OF SPILLWAY

SCALE 1" = 100'

700
0+00

5+00


DOWNSTREAM ELEVATION OF DAM

SCALE 1" = 100'

10+00

15+00

700



TYPICAL CROSS SECTION OF DAM


SCALE 1" = 40'

RECORD
DRAWINGS

11/17/41	Incoming service and conduit added	10	20
10/30/41	Fill for Operator's Quarters added	20	20
10/10/41	Drainage ditch added	20	20
5/14/41	Channel grade changed	20	20
10/20/40	Cleaning note added	12.6.41	20

CONNECTICUT RIVER FLOOD CONTROL BIRCH HILL DAM GENERAL PLAN




MILLERS RIVER MASSACHUSETTS
IN 50 SHEETS SCALE: 1" = 100 FT. SHEET NO 10
U. S. ENGINEER OFFICE, PROVIDENCE, R. I. JAN. 1940
SUBMITTED APPROVAL RECOMMENDED APPROVED



- FD-88-1 (PZ-11)
- FD-88-2 (PZ-10)
- FD-88-3 (PZ-15)
- FD-88-4 (PZ-14)
- FD-88-5 (PZ-12)
- FD-88-6 (PZ-13)
- FD-88-7 (PZ-16)
- FD-88-8 (PZ-17)

Piezometer Installation by
Atlantic Testing Laboratories, Ltd
10/18/88 thru 11/21/88


PIEZOMETER LOCATION PLAN



PIEZOMETER NUMBER (DATE INS.)	APPROXIMATE LOCATION	EL. OF TOP OF RISER	EL. OF SOUNDING *	ASSUMED ELEV. OF PLATE
1 (1941)	6+40 78'U/S	846.16	811.9	806.0
2 (1941)	6+40 CL	861.71	803.6	802.5
3 (1941)	6+40 69'D/S	844.46	811.2	805.0

* - FROM SOUNDINGS TAKEN IN 11/86



DEPARTMENT OF THE ARMY NEW ENGLAND DIVISION CORPS OF ENGINEERS WALTHAM, MASS.	
R.C.M./A.J.F. DES. BY	WATER RESOURCES DEVELOPMENT PROJECT CONNECTICUT RIVER BASIN
R.C.M. DR. BY	BIRCH HILL DAM
J.C.H. CK. BY	SECTION - APPROXIMATELY STA. 6+40 POOL LEVEL VS. PIEZOMETER READINGS
GEOTECH. ENG. BR. SCALE: AS SHOWN PLATE NO. 11 DATE: JULY 1988	




SECTION AT STA. 9+40 SCALE: 1"=50'

PIEZOMETER NUMBER (DATE INST.)	APPROXIMATE LOCATION	EL. OF TOP OF RISER	EL. OF SOUNDING*	ASSUMED PLATE EL.
4 (1941)	9+40 70'D/S	846.15	816.8	816
5 (1941)	9+40 CL	862.75	816.0	814
6 (1941)	9+40 78'U/S	846.17	816.4	816

* - FROM SOUNDINGS TAKEN IN NOV. 1986





DEPARTMENT OF THE ARMY NEW ENGLAND DIVISION CORPS OF ENGINEERS WALTHAM, MASS.	
R.C.M./A.J.F. DES. BY	WATER RESOURCES DEVELOPMENT PROJECT CONNECTICUT RIVER BASIN
R.C.M. DR. BY	BIRCH HILL DAM
J.C.H. CK. BY	SECTION - APPROXIMATELY STA. 9+40 POOL LEVEL VS. PIEZOMETER READINGS
GEOTECH. ENG. BR. SCALE: AS SHOWN PLATE NO. 12 DATE: JULY 1988	



PIEZOMETER NUMBER (DATE INST.)	APPROXIMATE LOCATION	EL. OF TOP OF RISER	EL. OF SOUNDING*	ASSUMED PLATE EL.
7 (1941)	12+43 75' U/S	844.83	814.5	811.0
8 (1941)	12+43 CL	862.36	814.6	812.0
9 (1941)	12+43 70' D/S	845.12	814.7	810.0

* - FROM SOUNDINGS TAKEN IN NOV. 1986




DEPARTMENT OF THE ARMY
 NEW ENGLAND DIVISION
 CORPS OF ENGINEERS
 WALTHAM, MASS.


R.C.M./A.J.F.
 DES. BY
 R.C.M.
 DR. BY
 J.C.H.
 CK. BY

WATER RESOURCES DEVELOPMENT PROJECT
 CONNECTICUT RIVER BASIN
 BIRCH HILL DAM
 CROSS SECTION - STA. 12+43
 POOL LEVEL VS. PIEZOMETER READINGS

GEOTECH. ENG. BR. SCALE: AS SHOWN
 PLATE NO. 13 DATE: JULY 1988



BIRCH HILL DAM, MA
PIEZOMETER INSTALLATION



STA 10+50

SCALE: 1"=20'

Birch Hill DAM, MA
PIEZOMETER INSTALLATION

SECTION 9

OTHER RECORDS TAKEN

a. Survey Notes & Data

Weather: windy.

200

Piezometer Locations/Elev.

U.S. Army Corps of Engineers

Birchkill Dam, Mass.


December 15, 1993

UN-1201910 3946

Horiz Horiz Difference
Angle Dist Elevation Rod III.

Note: Due to excessive instrument vibration from high winds, piezometer locations and elevations were also shot from PK-1 for verification.

P2-17	236.0002	143.15	-34.16	0.0
P2-16	2114813	86.61	-12.26	5.0
P2-15	1753317	70.50	0.38	5.0
P2-14	1444750	83.53	-6.17	5.0
Mon AB-3	092546	140.56	-0.47	5.0
P2-13	336.5188	304.01	-28.71	5.0
P2-12	349.5110	282.03	-13.55	5.0
P2-11	004818	278.74	-4.48	0.0
P2-10	090616	283.32	-10.85	0.0
Mon AB-2	034026	339.47	-0.39	5.0
Tot PK2				
BS PK-1	1H=4.80	210.50	+0.28	5.0
PK-2	1894426	140.54	1.00	5.0
PK-1	3423642	75.34	1.10	5.0
Tot AB-3				
BS AB-2	1H=4.67	200.12	0.48	5.0



Page	From	To	Diff.		
2	Page	Dist.	Elevation	Foot	
PZ-13	120 1055	137.74	-34.14	0.0	
PZ-12	143 3350	83.54	-19.17	0.0	
PZ-11	183 0258	68.59	-0.10	5.0	
PZ-10	212 5313	32.55	-11.25	0.0	
^{non} AB-3	342 1437	75.42	-0.94	5.0	
Z-14	350 2216	283.07	-6.54	5.0	
Mon AB-4	354 5614	272.73	-1.04	5.0	
PZ-15	358 5141	281.36	0.12	5.0	
PZ-17	22 1525	313.78	-34.67	0.0	
PZ-16	09 0955	287.58	-12.69	5.0	
Total PK-1					
BS PK-2	IH = 5.14 210.47 -0.27 : 5.0				

Page

3

Piezometer	Static Water from	Surface
Piezometer from (using)	Piezometer	to (from)
Pz 14-Oran - 0.40'	37.30'	-3.9
Grey - 0.32	39.45	
Pz 15-Oran - 0.15	37.6	-12.15'
Grey - 0.15	46.4	
Pz 16-Grey - 0.70	32.4	3.2
Orange - 0.79	33.1	
Pz 17-Or. - 0.21	17.0	2.9
Pz 17-Grey - 0.32	17.0	
Pz 10-Oran. - 0.12	40.15	3.2
Pz 10-Grey - 0.04	40.5	
Pz 11-Oran. - 0.30	46.7	12.15'
Pz 11-Grey - 0.25	47.5	-
Pz 12-Oran - 0.31	33.8	3.5
Pz 12-Grey - 0.85	(7.7)	
Pz 13-Oran 0.59	19.0	2.7
Pz 13-Grey - 0.60	19.1	

SPENDER F. THEW, P.E./L.S.
P.O. BOX 29
CANTON, N.Y.

Date: 01-03-89

Page: 1

Coordinate File: CKCD033.CRD
List of Coordinate Points
* Denotes Contouring Masspoint

Point ID	NORTH	EAST	ELEV	Descriptor
2	594979.8157	432164.0579	863.5650	MON AB-2
3	594780.6854	432144.9587	863.4550	MON AB-3
4	594581.7718	432124.8458	863.3470	MON AB-4
8	594854.4036	432129.4108	864.2250	PK 1
9	594645.0743	432108.0652	864.1250	PK 2
10	594918.8197	432181.0351	858.1100	PZ 10
11	594922.1730	432139.9891	864.2650	PZ-11
12	594926.2599	432086.8683	850.1950	PZ 12
13	594935.3726	432017.9822	835.2250	PZ 13
14	594571.9581	432148.2029	857.8250	PZ 14
15	594573.9832	432106.4358	864.4850	PZ 15
16	594576.5903	432055.1005	851.6700	PZ 16
17	594577.5567	431981.7164	834.6950	PZ 17
23	594780.6137	432145.0065	863.4250	MON AB 3 CHECK
24	594581.6976	432125.7950	863.3250	MON AB 4 CHECK
102	594979.8923	432164.0723	864.3150	MON AB-2 CHECK
103	594780.6636	432145.0412	863.4550	MON AB-3 CHECK
110	594918.2338	432181.0444	858.0700	PZ 10 CHECK
111	594921.6317	432140.2353	864.4550	PZ 11 CHECK
112	594926.3013	432086.7972	850.3750	PZ 12 CHECK
113	594935.3131	432017.6021	835.2150	PZ 13 CHECK
114	594572.2878	432149.0454	857.7550	PZ 14 CHECK
115	594574.5947	432106.3708	864.3050	PZ 16 CHECK
116	594576.4782	432055.1893	851.6650	PZ 16 CHECK
117	594577.4793	431981.8795	834.7650	PZ 17 CHECK

*Coordinates and elevation
as recorded were determined
from PK-1.*

*Coordinates and elevation
determined from PK-1.*

*See note on S.C.M.
notes page 1.*

SUMMARY TABLE
PIEZOMETER LOCATIONS AND ELEVATIONS
BIRCH HILL DAM, SOUTH ROYALSTON, MA

Identification FD# PZ#		Northing	Easting	E L E V A T I O N S			
				Top of Riser		Top of Protective Pipe	Dam Surface
				Lower Piezometer	Upper Piezometer		
FD-88-1	PZ-11	594922.17	432139.99	864.01	863.96	864.26	Flush 864.3
FD-88-2	PZ-10	594918.82	432181.04	858.07	857.99	858.11	854.9
FD-88-3	PZ-15	594573.98	432106.44	864.33	864.33	864.48	Flush 864.5
FD-88-4	PZ-14	594571.96	432148.20	857.50	857.42	857.82	854.0
FD-88-5	PZ-12	594926.30	432086.87	849.35	849.89	850.20	846.7
FD-88-6	PZ-13	594935.37	432017.98	834.62	834.64	835.22	832.5
FD-88-7	PZ-16	594576.59	432055.10	850.97	850.88	851.67	848.4
FD-88-8	PZ-17	594577.56	431981.22	834.38	834.49	834.70	831.8